



Universidade do Minho
Escola de Engenharia

Collaborative BIM-based workflows for a new
sustainable compression-only structural block
construction system

Lombe Mutale

**Collaborative BIM-based workflows for
a new sustainable compression-only
structural block construction system**



European Master in
Building Information Modelling

The European Master in Building Information Modelling is a joint initiative of:



Universidade do Minho

Univerza v Ljubljani



POLITECNICO
MILANO 1863




UMinho | 2021



Co-funded by the
Erasmus+ Programme
of the European Union

September 2021



Universidade do Minho

Escola de Engenharia

Lombe Mutale

**Collaborative BIM-based workflows for a
new sustainable compression-only
structural block construction system**



European Master in
Building Information Modelling

Master Dissertation

European Master in Building Information Modelling

Work conducted under supervision of:

Miguel Azenha

Bruno Figueiredo

Carlos Gomes (Tutor in Company)



Co-funded by the
Erasmus+ Programme
of the European Union

September, 2021

AUTHORSHIP RIGHTS AND CONDITIONS OF USE OF THE WORK BY THIRD PARTIES

This is an academic work that can be used by third parties, as long as internationally accepted rules and good practices are respected, particularly in what concerns to author rights and related matters.

Therefore, the present work may be used according to the terms of the license shown below.

If the user needs permission to make use of this work in conditions that are not part of the licensing mentioned below, he/she should contact the author through the RepositóriUM platform of the University of Minho.

License granted to the users of this work



Attribution

CC BY

<https://creativecommons.org/licenses/by/4.0/>

ACKNOWLEDGEMENTS

I would like to express my deepest gratitude to my supervisors Professor Miguel Azenha, Professor Bruno Figueiredo and Carlos Gomes who provided invaluable feedback and support throughout the dissertation period.

Many thanks to the Erasmus Mundus Programme of the European Union for the provision of a scholarship that funded my studies and made my life much easier.

Thank you to Professor Nuno Mendes who provided DIANA FEA advice and support; Renato Correia who was kind enough to allow the use of his C# script and tirelessly answered all my questions; Samuel Ribeiro at the University of Minho Design Institute and Benedetta Boso who assisted with the creation of the 3D printed prototype and photo montage and patiently made sure we got it right.

Further thanks to the BIM A+ staff and my fellow students in the BIM A+ 2020/2021 cohort for a memorable year, that was more than I could have ever imagined and will always cherish.

Last but not least, special thanks to my family and friends for their continuous support and encouragement.

STATEMENT OF INTEGRITY

I hereby declare having conducted this academic work with integrity. I confirm that I have not used plagiarism or any form of undue use of information or falsification of results along the process leading to its elaboration.

I further declare that I have fully acknowledged the Code of Ethical Conduct of the University of Minho.

Lombe Mutale

Lombe Mutale

RESUMO

Atualmente, a indústria da construção é a maior do mundo, sendo responsável por 8% das emissões de gases de efeito estufa, principalmente devido ao betão, que é o material mais comum usado na construção. O betão armado recorre a armaduras em aço, que estão particularmente sujeitas à corrosão quando ocorre fissuração e decorrente penetração de agentes agressivos do exterior. A corrosão generalizada do aço afeta a durabilidade de toda a estrutura, reduz sua vida útil e aumenta a necessidade de reabilitação e manutenção durante seu ciclo de vida. Uma alternativa interessante, em prol da otimização, durabilidade e minimização do desperdício de material, conceber estruturas de betão unicamente sujeitas a esforços de compressão e, evitando portanto a necessidade de utilização de armaduras. Isso pode ser alcançado através da aplicação de métodos de otimização da forma da estrutura. É também sabido que os sistemas pré-fabricados permitem otimização e aumento de produtividade na indústria da construção, por comparação com os métodos tradicionais de construção in-situ. Além disso, a digitalização por meio de BIM e processos de projeto computacional podem automatizar e auxiliar na redução de custos e garantia de qualidade.

Esta dissertação propõe o uso de betão de baixa resistência para criar estruturas pré-fabricadas de betão, sujeitas unicamente a esforços de compressão. Cada parte discreta da estrutura (módulos de cerca de um metro quadrado de área) é feita por meio de moldes flexíveis que se adaptam a uma ampla gama de geometrias. Os componentes estruturais são conectados por cabos de pré-esforço (em material não metálico, evitando efeitos de corrosão) que são instalados no local, criando assim um novo sistema de construção. Em suma, o sistema visa satisfazer os seguintes requisitos: i) ser autoportante durante a construção, ou precisando apenas de escoramento limitado; ii) comportamento estrutural otimizado (somente compressão - sem momentos de flexão), iii) alta durabilidade e longa vida útil (sem armaduras metálicas).

No âmbito da dissertação são utilizados algoritmos computacionais para criar uma forma estrutural de casca somente de compressão por meio de métodos conhecidos por 'form finding' no Rhinoceros / Grasshopper 3D. Uma vez obtida a forma estrutural geral, foi-lhe atribuída espessura e compartimentação (tecelagem), definindo assim seus elementos discretos. A sequência de construção dos elementos pré-fabricados foi implementada automaticamente com algoritmos de automação celular. Em seguida, foi criada uma ferramenta customizada que permite interoperabilidade automática do modelo criado para o software de análise estrutural DIANA e automatizou a análise em fases que incorporou a sequência construtiva. Posteriormente, foi usada a análise pelo método dos elementos finitos para avaliar o comportamento estrutural. Por fim, é proposto um fluxo de trabalho colaborativo entre engenheiros e arquitetos, rumo à definição conjunta de formas otimizadas com o procedimento desenvolvido nesta dissertação.

Por meio de um estudo de caso para testar a estrutura, os resultados mostram que o fluxo de trabalho proposto é viável, podendo ser aplicável a outras geometrias mais complexas. Refira-se que embora existam algumas tensões de tração presentes durante a construção em fases, elas podem ser quase eliminadas com o uso de suportes de construção provisórios (meros escoramentos tipicamente usados na construção) com pouco impacto nos custos e tempo de construção.

Palavras-chave: método dos elementos finitos, otimização de forma, interoperabilidade, pré-fabricação, modelação paramétrica)

ABSTRACT

Currently, the construction industry is the largest industry in the world and contributes 8% per year to greenhouse gas emissions mostly due to concrete which is the most common material used for construction. Reinforced concrete needs steel reinforcement which is prone to rust when the concrete cracks and deleterious materials reach the steel. Widespread steel corrosion affects the durability of the entire structure, reduces its service life, and increases the need for rehabilitation and maintenance during its lifecycle. An interesting alternative, for the sake of optimisation, durability, and material waste minimisation, would be to make concrete structures solely endure compression forces and hence avoid the need to use steel reinforcement. This can be achieved through applying form-finding methods to achieve optimised structural shapes. Precast systems can further optimise and increase the industry's productivity more than the traditional on-site construction systems can. Additionally, digitalisation through BIM and computational design processes can automate and assist in cost savings and quality assurance.

This dissertation proposes the use of low-strength concrete to create precast compression-only concrete structures. Each discrete part of the structure is made through flexible moulds that are adaptable to a wide range of geometries. The structural components are connected by prestressing cables (not made of steel and not prone to corrosion) which are installed in-situ thereby creating a new construction system. In short, the system aims to satisfy the following requirements i) self-supporting during construction, or only needing some propping ii) optimised structural behaviour (compression-only – no bending moments), iii) high durability and long service life (no reinforcement).

Computational and parametric design were used to create a compression-only shell structural shape through the Particle Spring form-finding method in Rhinoceros/Grasshopper 3D. Once the overall structural shape was obtained, it was thickened and tessellated thereby defining its discrete elements. The construction sequence of precast elements was implemented automatically with a cellular automata algorithm. Then, a custom tool was created that linked the structural shape generated to the structural analysis software DIANA and automated the phased analysis which incorporated the construction sequencing. Thereafter, finite element analysis (FEA) was used to assess the structural behaviour. Finally, a collaborative workflow was set up such that engineers and architects can work together to create the most optimal structural shape in a BIM environment.

Through a case study to evaluate the framework, results show that with the proposed workflow, any arbitrary compression-only structural shape can be defined using form-finding principles. FEA can be performed for structural analysis and a BIM model produced for construction. Although, there are some tensile stresses present during the phased construction they can be almost eliminated with the use of minimal construction supports.

Keywords: (FEA, form-finding, interoperability, modular construction, parametric modelling)

TABLE OF CONTENTS

1. INTRODUCTION.....	15
1.1. SCOPE AND MOTIVATION	15
1.2. OBJECTIVES AND METHODOLOGY.....	17
1.3. STRUCTURE OF DISSERTATION.....	18
2. SUSTAINABLE DESIGN AND CONSTRUCTION OF SHELL STRUCTURES USING DIGITAL PROCESSES & TECHNOLOGIES	19
2.1. INTRODUCTION.....	19
2.2. THE PRINCIPLE OF PERPECTUM	20
2.3. SHELL STRUCTURES.....	21
2.3.1. Definition, advantages and disadvantages.....	21
2.3.2. Form-finding methods for obtaining shell geometry.....	22
2.3.3. Structural analysis	24
2.4. MODULAR CONSTRUCTION SYSTEMS.....	26
2.5. DESIGN AND CONSTRUCTION OF SHELL STRUCTURES.....	28
2.5.1. Computational design and parametric modelling for shell structures	28
2.5.2. Prefabricated sequential construction.....	31
2.6. COLLABORATIVE BIM BASED WORKFLOWS	33
2.6.1. Digitalisation	33
2.6.2. Computational Design, Formwork development and physical prototyping.....	34
2.6.3. An integrated framework for multi-criteria optimization of thin concrete shells.....	36
3. PARAMETRIC MODELLING AND COMPUTATIONAL DESIGN TOWARDS MODEL GENERATION	39
3.1. INTRODUCTION.....	39
3.2. GEOMETRICAL CONCEPT FOR VAULT SYSTEM.....	39
3.3. OVERVIEW OF PARAMETRIC MODELLING AND COMPUTATIONAL DESIGN WORKFLOW	40
3.4. IMPLEMENTATION OF THE COMPUTATIONAL DESIGN MODEL	41
3.4.1. Structural equilibrium by form-finding.....	41
3.4.2. Thickening, tessellating and discretisation of the structure.....	43
3.4.3. Generation of cable curves	45
3.4.4. Creating the assembly sequence using a cellular automata algorithm	47
3.4.5. Connection and interoperability with BIM platform including level of information need	52
3.5. 3D PRINTING	54
4. STRUCTURAL ANALYSIS PROCEDURES.....	57
4.1. INTRODUCTION.....	57
4.2. STRUCTURAL CONCEPT OF THE CONSTRUCTION SYSTEM	57
4.2.1. Panel size and material.....	57
4.2.2. Post tensioning load	58
4.2.3. Temporary supports during construction	59

4.3.	INTEROPERABILITY TOOL FOR CONNECTION BETWEEN MODELLING PLATFORM AND STRUCTURAL ANALYSIS SOFTWARE.....	59
4.4.	DIANA FEA PROPERTY ASSIGNMENT AND PHASED ANALYSIS PROCEDURES	60
4.4.1.	Property assignment procedure.....	60
4.4.2.	DIANA Phased Analysis.....	61
4.5.	DIANA EXAMPLES	62
4.5.1.	Four-block model phased analysis	62
4.5.2.	Python scripting for DIANA	64
4.6.	SCRIPT FOR PROPERTY ASSIGNMENT AND CONSTRUCTION PHASING	65
5.	FRAMEWORK DEFINITION AND CASE STUDY	67
5.1.	INTRODUCTION.....	67
5.2.	FRAMEWORK FOR WORKFLOW WITH ARCHITECT AND STRUCTURAL ENGINEER	67
5.3.	CASE STUDY OF A NEW SUSTAINABLE COMPRESSION-ONLY STRUCTURAL BLOCK CONSTRUCTION SYSTEM	72
5.3.1.	Parametric modelling.....	72
5.3.2.	Structural description: supports, material properties and loading	76
5.3.2.1.	Boundary conditions.....	77
5.3.2.2.	Material properties.....	77
5.3.2.3.	Loads	78
5.3.2.4.	Load combinations	79
5.3.2.5.	Construction scenarios considered	79
5.3.3.	FEA modelling and analysis.....	80
5.3.4.	Results for Check 1: Self-weight only, no construction support and no phasing	80
5.3.5.	Results for Check 2: Construction phasing but no construction supports	81
5.3.6.	Results for Check 3: Construction phasing and construction supports	82
5.3.6.1.	Possibility of cracks during construction.....	82
5.3.6.2.	Possibility of instability due to interface tensions during construction	83
5.3.6.3.	Deflections and Bending moments.....	85
5.3.7.	Results for Check 4: Wind Load	86
5.3.8.	Results for Check 5: Snow load	87
5.3.9.	Photo montage of case study	88
5.4.	OTHER APPLICATIONS OF FRAMEWORK	88
5.4.1.	Exhibit A	88
5.4.2.	Exhibit B.....	90
5.4.3.	Exhibit C and Photo Montage	91
6.	CONCLUSION	95
	REFERENCES.....	97
	LIST OF ACRONYMS AND ABBREVIATIONS	101
	APPENDICES	103
	APPENDIX 1: PYTHON SCRIPT FOR DIANA AUTOMATIC PROPERTY ASSIGNMENT AND CONSTRUCTION PHASING	103

APPENDIX 2: DIANA MODELLING AND ANALYSIS PROCEDURE 107
APPENDIX 3: PART GRASSHOPPER CODE FOR FORM-FINDING AND SHAPE
GENERATION 116

LIST OF FIGURES

Figure 1 – Compression-only shell structure - Aichtal Outdoor Theatre in Germany (Adriaenssens et al., 2014).....	15
Figure 2 - Set of assembled panels as proposed by Perpectum (Azenha, 2019)	16
Figure 3 – Construction labour-productivity vs. manufacturing and total economy growth trend (Barbosa et al., 2017).....	19
Figure 4 – Photo example of corrosion-induced damage on a reinforced concrete marine structure (Alexander and Nganga, 2014).....	20
Figure 5 – Perpectum panel concept and 3D printed proofs of concept (Azenha, 2019).....	21
Figure 6 – Under construction and completed shell structure at the entrance of the Universal Oceanographic Park in Valencia, Spain (Tomás and Martí, 2010)	22
Figure 7 – Top and axonometric views for Form-finding example starting with a flat mesh/grid & supports at two opposite corners (Veenendaal and Block, 2012).....	23
Figure 8 - FEM Process (Schuster, 2017).....	25
Figure 9 – The Kresge Auditorium, Cambridge, 1955, by Eero Saarinen, as of 2003, with detail of support (Adriaenssens et al., 2014)	25
Figure 10 - Comparison of FEM results of Kresge Auditorium As-built shell and Optimised shell using form-finding (Goldbach et al., 2020).....	26
Figure 11 – The Striatus Bridge being built through the assembly of modules (Lomholt, 2021)	27
Figure 12 - Initial plan views and final 3D shape from form-finding computation (Vizotto, 2010).....	29
Figure 13 – Shell optimisation with different boundary conditions (Tomás and Martí, 2010)	30
Figure 14 - Result of form-finding using RhinoVAULT & Panelisation of shell (Hadilou, 2014)	31
Figure 15 - Illustration of LEGO-inspired blocks and assembled structure (Bao & Li, 2020)	31
Figure 16 - Lock Block Products (Lock Block, 2021)	32
Figure 17 - Large precast concrete panels on a truck (Shay Murtagh, 2021).....	32
Figure 18 – Overall framework and details of computational design optimisation steps (Kontovourkis et al., 2019).....	34
Figure 19 - 3D printed shell prototype with hexagonal tessellation (Adriaenssens et al., 2014)	34
Figure 20 - Schematic of adaptable mould (Borg Costanzi et al., 2018).....	35
Figure 21 - Interactive and iterative thin shell pre-design process (Gomes et al., 2018)	36
Figure 22 - Parameters and constraints for form-finding for a generic rectangular shape - Top view..	40
Figure 23 - Generative Schema of a regular 7x5 network, top view and axonometric view.....	42
Figure 24 - Grasshopper definition for the generation of a simple relaxed mesh through Kangaroo form-finding solver.....	42
Figure 25 – Form-finding mesh results with 3 varying inputs, axonometric view.....	43
Figure 26 – 3D view of gaps between panels resulting non-smooth curve from using Panelling tools	43
Figure 27 - Generative schema: Surface fragmentation, axonometric view.....	44
Figure 28 - Generative Schema: U/V Curves for Top and Bottom Surface, axonometric view	44
Figure 29 – 3D structure segmented into panels and plan view with labelling	44
Figure 30 - Panel and cable parameters and constraints.....	45
Figure 31 - Creation and selection of cable curves in U direction, axonometric view.....	45
Figure 32 - Creation and selection of cable curves in V direction, axonometric view.....	46

Figure 33 – Top and Bottom cable curves in U direction and labelling for each panel	46
Figure 34 – Left and Right cable curves in V direction and labelling for each panel	46
Figure 35 – Grasshopper cellular automata algorithm using the Anemone Plug-in	48
Figure 36 - Neighbours for cells based on maximum 8 neighbours and radius 1.5	49
Figure 37 - Neighbours for cells based on maximum 4 neighbours and radius 1.0	49
Figure 38 - Cell automata activation sequence – inner panels activated first	50
Figure 39 - 3D and Plan View labelled with Assembly Sequence (1)	51
Figure 40 - Cell automata activation sequence – outer panels activated first	51
Figure 41 – Axonometric and Top View labelled with Assembly Sequence (2)	52
Figure 42 - Rhino geometry in Revit before baking, axonometric view	52
Figure 43 - Revit geometry low level of detail, axonometric view	53
Figure 44 - Revit geometry with higher level of detail, axonometric view	53
Figure 45 - 3D printed blocks before assembly	54
Figure 46 - 3D printed blocks after assembly - Front view	54
Figure 47 - 3D printed blocks after assembly – axonometric view	55
Figure 48 – PT Block Free body diagram and stress interface calculations	58
Figure 49 - Summary of conversion process of cable curves from Revit to DIANA geometry	59
Figure 50 - Summary of the conversion process of a single panel from Revit to DIANA geometry ...	60
Figure 51 – DIANA example with four panels - Isometric and right view	62
Figure 52 - DIANA Stages of construction 1 to 2 for four-panel example	63
Figure 53 - DIANA Stages of construction 3 to 4 for four-block example	64
Figure 54 - DIANA single panel size 1m x 1m x 0.3m, axonometric view and properties	65
Figure 55 - DIANA Example block properties and Python commands	65
Figure 56 – Part of Python script setting up properties	66
Figure 57 – Framework for case study workflow	68
Figure 58 - Process 1: Geometry definition	69
Figure 59 - Process 2: BIM	70
Figure 60 - Process 3: Structural Analysis	71
Figure 61 – Preliminary sketch of Case Study from Process 1c	72
Figure 62 – Case study starting curves and resulting surface – Top view	72
Figure 63 – Case study support locations, springs, and force application positions – Top view	73
Figure 64 – Case study mesh and tessellated 300mm thick 3D shape – axonometric view	73
Figure 65 - Case study initial order BEFORE cellular automata algorithm – Top view	74
Figure 66 - Case study final order AFTER cellular automata algorithm – Top view	75
Figure 67 - Case study – Revit model and cutout showing PT cables, axonometric view	76
Figure 68 - Case study - Screenshots of 6 assembly stages while Python script is running in DIANA	76
Figure 69 – Bottom view and axonometric view of structure with permanent supports	77
Figure 70 - Bottom view showing permanent and temporary construction supports	77
Figure 71 - Wind Load regions for curved roofs according to EN 1991-1-4:2005	78
Figure 72 - Wind values and direction as applied in DIANA	78
Figure 73 – Uniform Snow load added to structure in DIANA	79
Figure 74 - Principal Stresses S1 - Self-weight only, no construction supports or phasing	81
Figure 75 - Principal Stresses S1 for Construction Stage 140 with no provisional supports	81
Figure 76 – Principal Stresses S1 for Check 3 during early construction (1)	82

Figure 77 – Principal Stresses S1 for Check 3 during construction (2).....	83
Figure 78 – Central Interface stresses during Construction Stage 140 (1)	84
Figure 79 – Central Interface stresses during Construction Stage 140 (2)	84
Figure 80 – Block A Interface stresses at Construction Stage 140.....	84
Figure 81 – Principal stresses S1 for Wind Load after construction	86
Figure 82 - Principal stresses S2 for Wind Load after construction.....	86
Figure 83 – Principal stresses S1 for Snow Load after construction	87
Figure 84 - Principal stresses S2 for Snow Load after construction.....	87
Figure 85 - Photo montage of case study, Parque da Cidade, Guimarães	88
Figure 86 – Exhibit A: Rhino 3D results	89
Figure 87 - Exhibit A: Autodesk Revit result – 3D model	89
Figure 88 - Exhibit A: DIANA result – 3D model	90
Figure 89 - Exhibit B: Rhino 3D result	90
Figure 90 - Exhibit B: Autodesk Revit Result.....	90
Figure 91 - Exhibit B: DIANA model	91
Figure 92 - Exhibit C: Panels in Rhino.....	91
Figure 93 - Exhibit C: Cables in Rhino	92
Figure 94 - Exhibit C: Revit model with two panels removed to show cables.....	92
Figure 95 - Exhibit C: DIANA model	93
Figure 96 - Photo montage of Exhibit C - application of the framework.....	93

LIST OF TABLES

Table 1 – Grasshopper Cellular automata algorithm task description	47
Table 2 - Case study - Material properties of concrete and steel	78
Table 3 - Load combinations.....	79
Table 4 – Construction scenarios	80
Table 5 - Interface tensile stresses and forces at 5 Construction Stages	85

This page is intentionally left blank

1. INTRODUCTION

1.1. Scope and motivation

Previous research showed that the construction industry is lagging in productivity and growth compared to other industries. This can be addressed with digitalisation of processes e.g. through incorporating Building Information Modelling (BIM) as well as the use of modular or off-site construction systems. Advantages of this include shorter construction and operational costs; reduced construction time; fewer unexpected costs for the client due to unforeseen issues on site; reduced energy consumption and better structural performance (Long *et al.*, 2014; Bertram *et al.*, 2019).

It is well documented that the main construction material, concrete, is a major contributor to greenhouse gas emissions (Belton, 2021). Additionally, even though no other material has been found to be more efficient for use in construction than concrete, steel reinforcement leads to corrosion, expansion, cracking and then deterioration of the concrete itself, thereby limiting the durability of reinforced concrete structures. However, the use of reinforcement is compounded when concrete structures are designed in a way that may be perceived as “unnatural”. With the use of form-finding, a “natural” compression-only shape (see Figure 1) can be found that can limit the use of reinforcement. Such shapes have been built before but with the aid of expensive formwork during construction (Adriaenssens *et al.*, 2014).



Figure 1 – Compression-only shell structure - Aichtal Outdoor Theatre in Germany (Adriaenssens *et al.*, 2014)

Various researchers have been looking into ways to optimise the current construction systems using precast and/or form-finding (Dallinger and Kollegger, 2008; Pedersen, Larsen and Pigram, 2015; Borg Costanzi *et al.*, 2018; Bao and Li, 2020). Realisation of the right construction system will assist in achieving the United Nation’s Sustainability Development Goals including “Sustainable Cities and Communities” and “Industry, Innovation and Infrastructure” to build sustainable and resilient infrastructure (United Nations, 2015).

There is work being done into optimising concrete mix and using more sustainable materials. This can be achieved for instance by substituting cement (whose production is carbon intensive) with fly ash from the coal industry or the slag from blast furnaces for improved strength and durability. Another (expensive) way is to physically capture the carbon produced during cement production and store it elsewhere (Belton, 2021). Other prefabrication manufacturers use steel reinforcement to connect precast elements such as the Lock Block company (Lock Block, 2021) which limits their durability.

Various limitations of the proposed design and construction systems exist as discussed forthwith. For example one author uses a procedure for form-finding with complex textual programming that cannot easily be followed other than by the originator (Vizotto, 2010). Some use BIM and an integrated approach but this is limited to the conceptual design stage (Gomes *et al.*, 2018).

Authors such as Kontovourkis *et al.* (2019) present a BIM-based computational design and optimisation framework using topology optimisation and incorporating construction considerations. Although they consider concrete modular elements, they do not consider construction supports required for shell structures. Additionally, they make use of a non-flexible formwork mechanism that is restricted to a Y-shaped element only (Kontovourkis, Phocas and Katsambas, 2019) unlike the flexible mould for the formwork of shell structures proposed in other literature (Borg Costanzi *et al.*, 2018).

More recently, the Striatum Bridge in Venice's uses extremely large concrete modules by 3D printing that require heavy lifting devices (Lomholt, 2021). On the other hand, Bao and Li (2020) propose the solution for the problem of connection and ease of assembly and disassembly of precast elements using much smaller brick-like components joined by pre-stressing cables. However, they neglect the optimisation aspect by not considering compression-only and form-finding structures (Bao and Li, 2020).

The Perpectum concept (Azenha, 2019) theorized but not implemented in 2019, seeks to address the problems identified. A sustainable, low-strength concrete precast compression-only structure that is virtually self-supporting during construction, is proposed (refer to Figure 2). This is achieved through a construction system whereby non-metallic cables connect the panels sequentially, during construction. Moreover, the panels are proposed to be sized at 1m x 1m x 0.3m such that they only require light lifting devices.




Figure 2 - Set of assembled panels as proposed by Perpectum (Azenha, 2019)

The current work further develops on Perpectum and addresses limitations of current systems as detailed in the objectives.

1.2. Objectives and methodology

This study proposes a new collaborative BIM-based, sustainable compression-only structural block construction system. Each discrete part (block) of the structure is made through flexible moulds that are adaptable to a wide range of geometry. The parts are connected by prestressed cables which will be installed in-situ thereby creating a new construction system. The system further satisfies the following:

- i) self-supporting or few supports during construction
- ii) optimised i.e. compression-only system
- iii) durable and long lasting with no steel reinforcement (prestressing cables made of a distinct non-ferrous material).

For the purposes of evaluating the proposed construction system, the objectives of the study are as follows:

- perform parametric modelling, computational design, and form-finding to produce a tessellated compression-only structural shape
- define a construction sequence using cellular automata principles
- define interoperability tools between the computational design program and BIM platform as well as between the BIM platform and (Finite Element Analysis) FEA software
- create a BIM model from the structural shape in the computational design program
- define the structural model from the BIM model and perform FEA to assess the structural behaviour of the construction system
- define a BIM-based framework for collaborative design between the structural engineer and the architect

Accordingly, the methodology entails the use of computational and parametric design to create a compression-only shell structural shape through the particle spring form-finding method. Once the overall structural shape is obtained, it is tessellated to define its discrete elements. Thereafter, FEA is used to assess the structural behaviour based on the construction sequence. Finally, a collaborative framework is presented such that the engineers and architects can work together to define and construct the most optimal structural shape in a BIM environment.

It is finally remarked that this dissertation does not address the technological aspects needed for the prefabrication of the modules for the system, neither from the point of view of the flexible moulds, nor from the point of view of the adaptable parts needed to materialize the hollow parts for the cables to pass.

1.3. Structure of dissertation

The layout of the thesis is as follows. Chapter 2 presents a literature review of sustainability and optimisation in the design and construction of shell structures. The principle of Perpectum, which was the inspiration for this work, is presented. This is followed by a general discussion on shell structures and modular construction systems. Next, these principles are refined and distilled with examples incorporating BIM processes and workflows.

Chapter 3 presents the parametric modelling and computational design methodology in this study using a simple example to explain the procedures. Rhinoceros 3D and plug-in Grasshopper 3D are used to conduct the form-finding and create the cellular automata algorithm for obtaining the construction sequence. A description of the connection tool from the computational design software to BIM platform is presented. The last section of this chapter shows photos of the 3D printed version of the example.

Chapter 4 describes the interoperability tool defined for the BIM platform to structural analysis connection. The chapter has a discussion on some of the properties to be used for the structural analysis in the software DIANA FEA. Subsequently, the script for automating the material property assignment and construction phasing is presented.

Chapter 5 presents the framework describing the collaborative workflow between the structural engineer and the architect to perform the design to produce the compression-only construction system. Thereafter, the framework is enacted with a case study including the parametric modelling, BIM, finite element analysis and results. Other applications of the framework are also briefly presented.

Finally, Chapter 6 concludes the work and presents recommendations and future work proposals.

2. SUSTAINABLE DESIGN AND CONSTRUCTION OF SHELL STRUCTURES USING DIGITAL PROCESSES & TECHNOLOGIES

2.1. Introduction

In recent decades, the construction industry has been criticized due to its continued use of high energy-consuming materials such as steel and concrete in a manner that is wasteful and neither optimised nor sustainable thereby limiting its productivity (Ribeirinho *et al.*, 2020; Belton, 2021; Webb, 2021). Moreover, unlike other manufacturing industries that have embraced digitisation and automation, the construction industry lags behind and has made little progress on this front (Barbosa *et al.*, 2017). As a result, the construction industry has been limiting itself in terms of productivity and growth thereby lagging far behind the manufacturing sector as well as the total economy trend as shown in Figure 3.




Figure 3 – Construction labour-productivity vs. manufacturing and total economy growth trend (Barbosa *et al.*, 2017)

The construction index of real gross value added per hour worked, only improved from 100 in 1995 to 110 in 2014, while manufacturing improved from 100 to almost 200 in the same time frame. Similarly, the compound annual growth rate for manufacturing was 2.6% higher than for construction in the same period. In fact, according to a study by the McKinsey Global Institute think tank (Ribeirinho *et al.*, 2020), the construction industry contributes 8% per year to greenhouse gas emissions compared to the aviation industry's much lower 2.5% (Ribeirinho *et al.*, 2020; Belton, 2021).

Other critical aspects of modern construction materials are their durability and life cycle. For instance, concrete has been the main material used for construction (Belton, 2021). The reason for this is its mechanical properties and ease of production and ability to be moulded to the desired geometry. Although some concrete structures such as the Pantheon in Rome, Italy have been standing for more than 2000 years, modern concrete structures require the use of steel reinforcement in addition to the concrete to resist external loading effects. The problem is that steel reinforcement is prone to rust and this can happen when the concrete cracks and there is ingress of deleterious materials that reach the steel

(refer to Figure 4). This affects the durability of the entire structure and reduces its service life or increases rehabilitation and maintenance costs (Alexander and Nganga, 2014).



Figure 4 – Photo example of corrosion-induced damage on a reinforced concrete marine structure (Alexander and Nganga, 2014)

Despite the challenges identified, it is possible to make construction more productive without compromising on sustainability through a few simple principles (World Economic Forum, 2018). The first basic principle relies on optimising the construction materials by changing its constituents and selecting more durable materials and minimising steel reinforcing, by using better structural shapes such as shell structures. The second principle consists of using modular or precast construction systems thereby making the construction process faster and more efficient. The third principle relies on shifting from on-site construction to off-site prefabrication and controlled sequential construction. Finally, the fourth principle is based on incorporating digitalisation, automation and robotics and embracing related technologies such as BIM, 3D printing and Digital Twin technologies.

In this regard, the present thesis has been inspired by, and developed within the framework of the ongoing research project called "Perpectum". Perpectum combines the Latin words "Perpectum" meaning everlasting and "tectum" meaning shelter (Azenha, 2019). The concept of Perpectum aims to follow the four principles just mentioned as will be shown in the following chapters.

This chapter reviews the current state-of-the art of shell structures, their sustainable design and how various authors are incorporating BIM digital processes in their design. It is therefore organized as follows. Section 2.2 outlines the Perpectum project. Shell structures are the basis of the Perpectum project due to their efficiency and the main structural system being researched and so Section 2.3 presents and discusses the main principles on which shell structures rely on. Section 2.4 focuses on modular construction systems for reasons discussed in this introduction. Sections 2.5 and 2.6 combine the topics presented and look at ways that they can be further optimised with computational design and BIM-based workflows applied to shell structures.

2.2. The principle of Perpectum

Perpectum is a research proposal that addresses the various challenges that will be highlighted in the literature review including steel leading to reduced durability and the expenses related to use of

formwork when constructing shells and free-form structures. Perpectum results in a more efficient and cost-effective construction by using i) sustainable concrete with no rebar thereby avoiding corrosion and leading to indefinite durability ii) customisable moulds for concrete structural panels iii) permanent pre-stressing cables, and iv) Integrated Project Delivery (Azenha, 2019).

Perpectum proposes the use of prefabricated concrete panels without rebar which are produced from customisable moulds. The panels can then be constructed sequentially using pre-stressed cables to produce compression-only free form shell structures – refer to Figure 5.




Figure 5 – Perpectum panel concept and 3D printed proofs of concept (Azenha, 2019)

The member connection is partly inspired by Dallinger & Kollegger (2008) who proposed precast textile reinforced concrete panels constructed using post-tensioning cables that pass-through ducts in the panels. The pre-stressing ensures stability during construction without the need for extensive and complex formwork or construction supports. Theoretically, this pre-loading would result in the structure being in compression with minimal deformation that acts like a single monolithic structure despite being made up of separate panels. Emphasis has also been placed on having enough pre-stress such that there is no tension at the interface between the panels which would cause instability of the structure (Dallinger and Kollegger, 2008). Additionally, the pre-stressing cables are not steel but rather maritime cables that are non-corrodible and will therefore be highly durable (Azenha, 2019). These principles will be expanded on further in the chapters that follow.

2.3. Shell structures

2.3.1. Definition, advantages and disadvantages

Shell structures are large with a thickness much smaller than their other dimensions. They transmit forces primarily through a membrane action rather than bending moments. The advantages of shell structures are that, first, they are aesthetically pleasing, natural looking forms. Secondly, large open spaces and areas can be created without the need to use supports in between them. Third, due to their thinness, use of the membrane action and the high strength to weight ratio, the design is more efficient, and less material can be used, thereby making them more environmentally friendly (Adriaenssens *et al.*, 2014; Zingoni and Enoma, 2020).

However, shell structures, particularly concrete ones, have some disadvantages which have led to their decline in use and popularity. The main reason for this is, the cost of the formwork which can be as much as a third of the total concrete cost on the project or 15% of the total construction cost. This cost is usually due to the difficulty and complexity in setting up and dismantling the intricate formwork and scaffolding (Nassar and Aly, 2012; Zingoni and Enoma, 2020) and is therefore significantly increased when it comes to shapes from form-finding processes (Tomás and Martí, 2010; Kontovourkis, Phocas and Katsambas, 2019) as shown in Figure 6.



Figure 6 – Under construction and completed shell structure at the entrance of the Universal Oceanographic Park in Valencia, Spain (Tomás and Martí, 2010)

Nonetheless, nowadays, innovative options for customisable formwork are being considered with the help of technology, computational design and inspired by the textile industry, but these are yet to become mainstream (Borg Costanzi *et al.*, 2018; Popescu *et al.*, 2021). Alternatively, there are suggestions to have dual purpose shell structures to justify the cost of the formwork (Zingoni and Enoma, 2020).

Another disadvantage is that if the shell is too thin, buckling problems can arise. Studies suggest that this issue can be overcome by increasing the shell thickness, using a material with a higher elastic modulus or increasing the geometric curvatures (Tomás and Martí, 2010). The other challenge is how to produce the geometry of a shell structure that ensures optimal structural behaviour. This is where form-finding comes in.

2.3.2. Form-finding methods for obtaining shell geometry

There are two main methods to design a shell structure with a funicular shape. The first concerns the use of mathematical formulas that lead to the definition of geometries based on parabolas, spheres etc. However, if these “unnatural” shapes are used, extra reinforcement or edge beams are required to overcome the hoop stresses experienced in some areas and avoid excessive cracking during the life of the structure. The second method uses form-finding processes either from numerical means or by physical models as was popularised by Heinz Isler and Antoni Gaudí. The latter method creates tension-only geometries which can be inverted to create compression-only geometries inspired by Richard Waller’s statement “As hangs the flexible line, so but inverted will stand the rigid arch” and Hooke’s law of inversion. However, although useful for visualisation and conceptual design purposes, physical models have the limitation that the forces on the structure depend on the material and this cannot be easily factored into the process and therefore numerical calculations are required for verification. The alternative would be to create a scale replica of the structure, but this would be expensive. Advantages

of form-finding using numerical means are that it allows the consideration of material properties, computational design can be used, and more shapes can be found (Veenendaal and Block, 2012; Adriaenssens *et al.*, 2014; Zingoni and Enoma, 2020).

Form-finding can be described as an iterative process used to find the optimal shape (no bending moments, axial forces only) in an initial usually flat system (shell or grid) of particles, connected by springs, with certain boundary conditions and characteristics, by applying loads to the particles (refer to Figure 7). Essentially, the goal is to use the *forces to find the form* as opposed to traditional design methods that first start with the shape and then find the forces on the shape. Form-finding can be achieved traditionally, using methods such as the Particle Spring system, Dynamic Relaxation Method and Force Density Method (Adriaenssens *et al.*, 2014; Congiu, Fenu and Briseghella, 2021).




Figure 7 – Top and axonometric views for Form-finding example starting with a flat mesh/grid & supports at two opposite corners (Veenendaal and Block, 2012)

The Particle Spring Method is a dynamic equilibrium problem where the particles are given a mass while the springs have a stiffness and length. Thereafter, loads are applied onto the particles which cause displacements of the particles and elongation or reduction of the springs. The goal is to iterate until equilibrium is achieved i.e. the sum of applied loads equates the sum of internal forces. Despite being a dynamic equilibrium method which are the most efficient in terms of CPU usage, the method is seen as being overly complex with its use of multiple parameters (Veenendaal and Block, 2012; Adriaenssens *et al.*, 2014; Congiu, Fenu and Briseghella, 2021).

The Force Density Method is a geometric stiffness method whose underlying principle is the force density or tension coefficient which equates to force divided by the length of a bar. The method makes use of a linear system of equations. It initially involves the definition of the boundary conditions and the typology; this is followed by the definition of the force densities and the loads. These inputs are then used to calculate the displacements. The process is iterated until equilibrium is found. The method has the advantage that the material stiffnesses and properties considered are only considered at the end which makes it easier to compute. Nevertheless, the method has been criticised as not being constructable and being only suitable for preliminary purposes. Another criticism is that the “force density” coefficient is not an intuitive parameter compared to other well-known parameters such as forces (Veenendaal and Block, 2012; Adriaenssens *et al.*, 2014).

The Dynamic Relaxation Method was invented by Alistair Day. It is also a dynamic equilibrium method that makes use of nonlinear equations and the principle of Kinetic Energy (KE) with the nodes initially at rest (velocity, $v = 0$) and the $KE = 0$. Then a load is introduced to the system which leads to residual forces which depend on the axial forces and shear forces and leads to a new velocity and kinetic energy for each node. This is then used to calculate the new KE in the system and the process is repeated until convergence occurs where the new and old KE are the same i.e. equilibrium (Veenendaal and Block, 2012; Adriaenssens *et al.*, 2014).

Other form-finding methods exist in the literature such as graphic statics diagram subdivision (Akbarzadeh, Van Mele and Block, 2014), the Thrust Network Analysis (Rippmann and Block, 2013) which is a type of graphic statics, as well as shell structures topology design all of which focus on generating funicular structural shapes by using axial diagrams. Veenendaal & Block (2012) and Adriaenssens *et al.* (2014) provide a comprehensive study on the topic of form-finding.

2.3.3. Structural analysis

Once the form (geometry) has been obtained, as explained in Section 2.3.2, the next step is to conduct the structural analysis. Structural analysis involves the determination of the internal forces in the structure due to the applied loads. The goal is to determine whether the structure has the capacity to support the loads based on the structure’s material strength and stiffness, supports and boundary conditions. For static structures this is done by satisfying equations of i) *equilibrium* of applied loads and internal forces ii) *compatibility* of displacements between elements iii) *constitutive* relations to satisfy the principles of stress and strain of the elements (Adriaenssens *et al.*, 2014).

The Finite Element Method (FEM) of structural analysis is most used due to its applicability to structures of different boundary conditions, shapes and sizes. It simplifies complex problems by focussing on a small part of the structure at a time. Basically, once the problem is identified in terms of the knowns and unknowns, the FEM procedure (refer to Figure 8) requires the structure under analysis to be idealised and split into small (finite) elements. Then the three equations described in the previous paragraph, are solved based on the loads on each element and its support and boundary conditions. Thereafter, the equations for each element are summed up to find the solution for the whole structure.




Figure 8 - FEM Process (Schuster, 2017)

As can be predicted with FEM, the smaller the elements the closer to the correct solution but with a limit. The method remains an approximation of the actual solution and “mesh convergence” is normally advised to test out different element sizes to determine if there is a big difference in results. Unless extremely small elements are used, inevitably the FEM model geometry and the CAD model differ, especially for curved structures. However, if the structure is large, this will take high computing power and plenty of time (Bathe, 2010; Schuster, 2017). During the post-processing, the internal forces, or results such as bending moments, stresses and displacements can be obtained. As can be seen in Figure 9 and Figure 10, a slight change in shape from shape optimisation or form-finding processes can lead to more favourable FEM results than a shape from other design processes. In the constructed shell, which is a segment of a sphere, edge beams and complex connections were required to transfer the excessive forces at the corners, but these could have been avoided by using shell optimisation as shown in the diagrams on the right of Figure 10.




Figure 9 – The Kresge Auditorium, Cambridge, 1955, by Eero Saarinen, as of 2003, with detail of support (Adriaenssens et al., 2014)




Figure 10 - Comparison of FEM results of Kresge Auditorium As-built shell and Optimised shell using form-finding (Goldbach et al., 2020)

More recently, the Iso-geometric analysis (IGA) method has been identified as an alternative to the FEM. The method borrows heavily from FEM but has the advantage that it uses the same method of geometry production as CAD models i.e. Non-Uniform Rational B-Spline (NURBS) curves which are based on control points. Mesh refinement is carried out by using more control points which results in more accurate results but crucially does not change the shape, unlike the FEM (Hughes, Cottrell and Bazilevs, 2005; Goldbach *et al.*, 2020). IGA is something to look out for in the future, but for now FEM remains the standard way of carrying out structural analysis for complex structures.

2.4. Modular construction systems

The manufacturing industry has embraced the LEAN and SCRUM methodology from the software industry. Their main focus is to reduce waste in all forms and focus on essentials by improving communication, identifying possible impediments and promoting quick decision-making (Schwaber and Sutherland, 2015). Some of these theories and practices are being incorporated into the construction industry with the use of technology (BIM) and factories to manufacture the product i.e. prefabrication or modular construction. Modular construction refers to (Iacovidou *et al.*, 2021):

“off-site manufacture of prefabricated building components and units assembled together on-site”

Recently, the Striatus Bridge project (2021), developed by the Block Research Group (BRG) at ETH Zurich and Zaha Hadid Architects Computation and Design Group (ZHACODE), in collaboration with incremental3D (in3D) and Holcim, exemplifies the potential of off-site manufacture of prefabricated building components and units assembled together on-site (Lomholt, 2021). The Striatus Bridge is an arched, unreinforced masonry footbridge composed of 3D-printed concrete blocks assembled without mortar, installed at the Giardini della Marinaressa during the Venice Architecture Biennale, 2021 (Figure 11). Although it is not a shell structure it is a representation of modular construction systems which are of interest.



Figure 11 – The Striatu Bridge being built through the assembly of modules (Lomholt, 2021)

On-site construction has been the *modus operandi* in the construction industry for centuries. However, off-site or prefabrication systems are becoming more prevalent. For example, the permanent prefabrication market share in North America increased by 50% in the years between 2015 and 2018 (Ribeirinho *et al.*, 2020); currently, up to 80% of Scandinavian new houses manufactured off-site; and in the UK, 15000 modular houses are constructed each year (Iacovidou *et al.*, 2021). This is due to the many advantages of prefabrication including (Bertram *et al.*, 2019):

- a) Acceleration of project timelines by up to 50%
- b) Increased profits of up to 20%
- c) Significant construction cost savings
- d) Less waste and more sustainable designs

Another advantage is better quality control on the product by shifting the focus to an integrated design approach involving multiple stakeholders. This reduces the possibility of making costly mistakes i.e. when design decisions are made upfront, they are less costly than if made later on during the project such as during construction. There is also increased safety since the product can be manufactured in a controlled environment. Additionally, construction is quicker since the products can be delivered to site in the order in which they are required and quickly assembled. Furthermore, if it is a dry connection, there is no need to wait for the concrete to achieve enough strength before installing the next elements. And finally, automation of production can occur using machines in the factory (Lopez and Froese, 2016; Bertram *et al.*, 2019).

Despite this, modular construction has its own problems and challenges especially those related to transportation and others such as (Polat, 2008; Iacovidou *et al.*, 2021):

- a) High costs to transport components to site
- b) Local restrictions on truck weights
- c) Restricted vehicular load access on certain roads
- d) Restrictions on the size of the parts that can be carried at any one time
- e) Job loss for on-site trades such as masons, bricklayers, plasterers

Besides, it has recently been reported that two modular constructed large buildings in the United Kingdom (UK) caught fire and were destroyed. It is suspected that this was due to unseen cavities in the structure that allowed the fire to spread easily and that were brought about by the modular construction

(Stout, 2021). This suggests that connections between the prefabricated components in modular construction are of significant importance and will be discussed further in this thesis.

Still, Iacovidou et al., (2021) argue that making use of digital technologies in modular construction will affect sustainability, productivity, and resource efficiency in the whole construction value chain. Essentially, digitalisation in that area will have and should have domino effect into other areas of the construction industry, encouraging an integrated approach and making disasters like the recent fires in the UK, unlikely. It is perhaps for this reason that *Modular Integrated Construction* (MIC) is “the future of buildings” with various construction stakeholders involved from early in the design stage and the use of digital technologies (Abdelmageed and Zayed, 2020).

2.5. Design and construction of shell structures

2.5.1. Computational design and parametric modelling for shell structures

Due to the complexities of shell structures, it is time consuming to conduct the structural analysis and design calculations by hand. For this reason, computational design and parametric modelling have been co-opted into the design process to take advantage of the computer’s abilities and to be able to make changes easily. In his doctorate thesis, Davis (2013) discusses how there is contention about what parametric modelling is and how various authors have asserted that all design is parametric. But Davis (2013) argues against this and insists on the uniqueness and richness of parametric design as opposed to just stemming from the mathematical sense of the word “parametric” and being synonymous with change.

Parametric modelling is the use of the relationships between different parts of the model i.e. parameters to enable quick changes during the modelling process or (Stasiuk, 2018):

“a set of equations that express information regarding the deployment of an architectural information system, as explicit functions of a number of parameters”

The beauty of parametric modelling is that it requires the designer to fully understand the design and how it works. This will reduce the likelihood or necessity of changes later on during the project when it will prove most costly, as mentioned before (Davis, 2013).

Computational design makes use of parametric models to perform (Stasiuk, 2018):

“explicit transformative operations on parameters through the use of algorithms in pursuit of a design outcome”

Both parametric modelling and computational design are particularly useful for the design of shell structures using the form-finding method. Many parameters can be adjusted, and computational power can be used to come up with an infinite number of possible solutions and then further optimisation can be carried out to obtain the best solution through what is called generative modelling (Stasiuk, 2018). These methods normally require a level of programming knowledge to take full advantage of their capabilities and lessen the repetitive tasks involved once parameters are changed. Programming can be done either textually using an extensive list of languages (refer to Stasiuk (2018)) such as Python or

C++. Alternatively, for non-IT experts in the AEC industry, visual programming for example using Autodesk Dynamo or Grasshopper 3D is available but these may be expensive and more limited in capacity.

To overcome these costs, Vizotto (2010), used mathematical programming to come up with his own computational model to produce free-form optimised geometries inspired by Heinz Isler and perform structural calculations using the membrane theory of shell structures and the finite element method. The method starts with a simulated horizontal, plane surface, flexible membrane of any shape. Boundary constraints, self-weight and forces are then applied. This leads to iterations to obtain the optimal deformed shape of the structure by considering the structural equations and the FEM method in Section 2.3.3 and strain energy. This method is similar to the Dynamic Relaxation Method mentioned in Section 2.3.2. Under gravitational loading, the resulting shape is a tension structure which is inverted to produce compression-only vaults from defined envelopes as shown in Figure 12.




Figure 12 - Initial plan views and final 3D shape from form-finding computation (Vizotto, 2010)

As can be seen, depending on the initial shape and the position of the supports, different shapes can be generated. Still, despite the savings cost, the proposed method is complex to implement and using proprietary software would be easier. The method's results are comparable with other software results and physical methods so, can be used as a check to ensure a model is working as desired (Vizotto, 2010).

In contrast, around the same time, other authors also came up with their own methods for form-finding (Tomás and Martí, 2010). In the study, they set up a system of objective functions and make use of the strain energy (SE), weight and tensile stress on the faces of the shell to obtain optimal mechanical functioning based on a set of geometric variables for the defined parametric model. This is comparable to the Vizotto (2010) model except that the equations are solved in the optimisation module of ANSYS

software which is a CAD and engineering simulation software. Some of the results from this method are presented in Figure 13 where the given geometry is subjected to a vertical uniform load of 5kN/m^2 and the concrete shell is 50mm with a Young's module of 30 GPa and Poisson's ratio of 0.2 .




Figure 13 – Shell optimisation with different boundary conditions (Tomás and Martí, 2010)

In their work, the authors present a case study of a free form structure that is symmetric. They circumvent the problem of having a large model by using the symmetry to only analyse a part of the structure and reduce computational time. As expected, the results from the subsequent FEM reveal that using form-finding improves the structural performance of shell structures (Tomás and Martí, 2010).

On the other hand, authors such as Congiu et al. (2021) and Hadilou (2014) make use of proprietary software for the form-finding. Congiu et al. (2021) compare the Thrust Network Analysis using a tool integrated into Rhinoceros 3D called “RhinoVault”, with the Particle Spring method described in Section 2.3.2, using the Rhinoceros 3D plugin Grasshopper 3D’s Kangaroo component. In the latter procedure, an initial surface and mesh with defined particles and springs are created. Then the Kangaroo component, which is a physics simulator, iterates to find the resulting optimal shape based on the starting mesh, applied loads, spring stiffness and boundary conditions.

The study by Hadilou (2014) also makes use of RhinoVAULT to obtain shell geometry through form-finding. Once the shape is obtained, it can then be thickened and tessellated through computational design to obtain the 3-dimensional shape of the structure (refer to Figure 14). This can then be structurally designed and analysed, as discussed previously. Both studies are limited to conceptual design stages and make little mention of incorporating the structural analysis aspect in their workflow. This will be discussed in the following section.




Figure 14 - Result of form-finding using RhinoVAULT & Panelisation of shell (Hadilou, 2014)

2.5.2. Prefabricated sequential construction

In recent years, many prefabricated sequential construction methods have been proposed. As an example, Bao & Li (2020) propose the use of LEGO-inspired sustainable structures that can be assembled or disassembled as per the structural requirements and most importantly, in a sequential way. The authors are advocating for precast and using the LEGO method to i) make the connection between elements quicker with dry joints, and ii) reuse structures by disassembling the elements and assembling them elsewhere (refer to Figure 15).




Figure 15 - Illustration of LEGO-inspired blocks and assembled structure (Bao & Li, 2020)

In contrast to wet joints, the use of dry joints means there is no need to wait for concrete to dry on site. What is more, the method makes the blocks re-usable and therefore more sustainable and cost effective. In this case they use what they call “bendable concrete” which resists tension rather than rebar for improved durability and increased structural efficiency. They also use post tensioned (PT) cables to reduce cracking and bolts for the connections (Bao and Li, 2020).

The system seems to have some restrictions and flaws such as the cost of production of the concrete, applicability only to certain structures that have an overall rectilinear shape and the need for complex

algorithms to establish the correct assembly and disassembly procedure. The need for having customised moulds for each block also significantly increases the time required to produce the blocks. But the authors argue that the production time can be reduced in future with the use of 3D printing (Bao and Li, 2020).

Companies like Lock Block Ltd and Shay Murtagh Ltd are at the forefront of the precast construction industry in Canada and Ireland & UK respectively. Lock Block Ltd is committed to sustainability and claim to use “100% recycled aggregates and sand”. They use block units with connection keys at the interface to ensure robustness which can be further strengthened by connecting them with rods. The panels apply to various structural types, such as retaining walls, tunnels, overpasses etc. They are also easily assembled and disassembled; are reusable and have the advantage that no expensive scaffolding is required for construction (Lock Block, 2021). Regardless, their panels and construction systems are limited to specific structural types and would not be suitable for the free-form structural types being discussed in this thesis.




Figure 16 - Lock Block Products (Lock Block, 2021)

In comparison, Shay Murtagh Ltd has a wider applicability than the Lock Block system. They focus on larger elements consisting of precast beams, box culverts, precast tanks, or bespoke precast concrete and buildings by defining the individual precast panels that will form the building. Moreover, they consider a holistic view and design optimisation, addressing some of the challenges mentioned in Section 2.4 such as space on site, cost, constructability, sustainability. For instance, they plan and optimise the sequence of construction based on panel manufacture time at the factory, transportation to site, space on site and installation time (Gomes, 2021; Shay Murtagh, 2021). However, the construction system sometimes involves grouting or wet connection and propping of panels that requires waiting for hardening before constructing the next levels.



Figure 17 - Large precast concrete panels on a truck (Shay Murtagh, 2021)

2.6. Collaborative BIM based workflows

A collaborative BIM based workflow uses an integrated approach whereby multiple stakeholders in the AEC industry collaborate with digital tools and processes to design and construct a structure. This is particularly useful for complex shell structures as explained in this literature review.

2.6.1. Digitalisation

Digitalisation is the integration of digital technologies in processes that were previously analogue media-based processes. It is imperative for the AEC industry to embrace digitalisation to be more productive and increase innovation. It can be achieved with the use of BIM which will encourage collaboration and integration of multidisciplinary teams (World Economic Forum, 2018).

For example, construction drawings in the past were drawn by hand and physically handed to the contractor to conduct the construction. Nowadays, the situation is completely different with the use of either Computer-Aided Design (CAD) or Building Information Modelling (BIM) processes to perform the same task, thereby optimising and making the process quicker and more efficient and minimising mistakes. In the same way, engineers used to design on paper. While this is still the case sometimes, often, the design is conducted on a computer using computer programs that automate and quicken the design process. Similarly, the prefabrication can be automated, as is done in the automotive industry, rather than done manually (Bertram *et al.*, 2019).

During construction, automation can also be achieved using technologies such as 3D printing. This will become important particularly in the construction industry is afflicted by labour shortages (Turner & Townsend, 2018) a gap which can be covered by digital manufacturing processes. Digitalisation is relevant because it also allows the concept of “building it twice” which reduces the possibility that mistakes are made that will affect the construction process. Chuck Eastman in his prescient work (Eastman, 1974) describes a Building Description System (BDS) which is a large digital database of objects and their properties and their relationships with each other representing objects in a real building. The BDS has the following properties (Eastman, 1974):

- Change of item properties in one part of the drawing leads to automatic updates in all the other elevations, plans etc. ensuring efficiency and reducing redundancy found in paper drawings
- Object-oriented (borrowed from programming with properties such as inheritance and abstraction) database rather than line-based with construction item libraries to choose from
- Embedded metadata about the object provided by the manufactures for design, construction and facility management purposes
- Numerical analysis of the building’s properties
- No obsolete information, information is always available and current
- Automation of quantity take-offs, building code checks and clash detection

This is the basis for what is called BIM today. For instance, 3-dimensional models can be set up with object libraries available in proprietary modelling platforms like Autodesk Revit as well as online with manufacturers details. It is possible to include geometrical and metadata of objects and functionalities that dwarf the capabilities of CAD. The 3D model can have BIM uses such as MEP modelling, Structural

modelling, and analysis as well as Energy analysis and Facility Management. The goal of BIM is to bridge the islands or silos of automation of AEC disciplines and enable accurate and consistent communication and flow of information through all the phases of a project using a digital 3-dimensional model (World Economic Forum, 2018).

2.6.2. Computational Design, Formwork development and physical prototyping

Kontovourkis et al., (2019) propose a computational design and optimisation framework linked to a customisable modular formwork and automated fabrication of shell structures. The goal is to minimise material waste, consequently reducing cost and the environmental impact of construction. The construction automation also leads to decreased material and energy consumption, as well as increased construction quality and accuracy. Their BIM-based workflow involving architects, engineers and contractors is presented in the form of the framework shown in Figure 18.




Figure 18 – Overall framework and details of computational design optimisation steps (Kontovourkis et al., 2019)

In their framework, the first part is the computational design optimization where the architect performs the form-finding of the structure. Secondly, the linear static structural analysis is conducted by the structural engineer in tandem with the topology optimisation and the parametric design by the architect. Third, once the geometry is finalised, the detailed design is carried out.



Figure 19 - 3D printed shell prototype with hexagonal tessellation (Adriaenssens et al., 2014)

This part also includes the tessellation process where the structure is subdivided into segments like the partitions of the shell of a tortoise. Though in this case the designer can select the type of shape of the units e.g. rectangular, hexagonal, isosceles triangles, etc. as seen in Figure 14 and Figure 19 (Kontovourkis, Phocas and Katsambas, 2019).

In the study, the surface obtained from form-finding is tessellated into square cells that are then offset to form a 3D structure. Through topological optimisation, the square cell becomes a Y-shaped unit which is defined as reinforced concrete for the structural analysis. The next part is the development of the semi-automatic formwork mechanism that can adjust its shape according to the tessellated unit. Nonetheless, the mechanism that was developed for the formwork is limited to the Y-shaped concrete components in their study and is not configurable for other tessellated shapes (Kontovourkis, Phocas and Katsambas, 2019).

A more sophisticated method presented by Borg Costanzi et al. (2018) uses 3D printing and allows the production of structures of any shape by casting its constituent concrete panels onto a flexible and adaptable mould rather than a flat plane – refer to Figure 20.




Figure 20 - Schematic of adaptable mould (Borg Costanzi et al., 2018)

The authors also make use of Grasshopper 3D to create the geometry and a custom workflow from design to production and assembly to create the structure. However, in the study the authors neglect to address the complexity of the required construction supports for shell or free-form structures. They also neither discuss the structural robustness of the solution nor the type of connection between the panels in detail (Borg Costanzi *et al.*, 2018).

The last part of the work by Kontovourkis et al. (2019) is the physical prototyping where each unit of the structure is brought to life through adjusting the shape of the formwork, casting the concrete then removing the unit from the mould, before assembling the units to form the structure. The authors envision that the units will be precast. Once on site, sequential construction of the units will occur with bracing and supports to hold the structure in place until it is completed (Kontovourkis, Phocas and Katsambas, 2019).

The main advantage of the proposed workflow is the form-finding and topology optimisation which ensures material optimisation. Another advantage is the semi-automated nature of the formwork for the

concrete casting and the use of precast panels to save on time and cost. Despite this, the paper contains a glaring omission which is that the complexity and expense of construction supports for shell structures is not addressed (Kontovourkis, Phocas and Katsambas, 2019).

2.6.3. An integrated framework for multi-criteria optimization of thin concrete shells

In their work, Gomes et al. (2018) propose an integrated framework for collaboration of the architect and engineer to produce a conceptual design of a shell structure. The framework allows for a quick generation and structural assessment of different 3D shell geometries, including cost and safety considerations to assist in accelerated decision making – refer to Figure 21.




Figure 21 - Interactive and iterative thin shell pre-design process (Gomes et al., 2018)

The paper proposes a methodology composed of three interlinked and iterative processes. In the first process, the boundary conditions and other requirements are defined, and a form-finding process is carried out to obtain the first shell shape. In the second process, a parametric model is created that allows the first shape to be changed easily to assess how these changes affect the defined requirements. The third and final process is computational design, which allows the computer to come up with unique solutions that are structurally optimal (Gomes *et al.*, 2018).

This last process uses a genetic algorithm that is provided with an initial population of possible solutions to iterate through and mutate based on provided goals and constraints to output the most optimal solutions. In the study, the goals were optimal structural performance and minimisation of cost. The

final part of this process is selection of a final structural shape based on a structural analysis that meets all design requirements (Gomes *et al.*, 2018).

The study shows that custom tools are sometimes necessary to perform certain tasks that go beyond the capabilities of proprietary software. This can be achieved by accessing the proprietary software's API and/or using programming languages such as C# and Python. In the study, a component was created in C# that can obtain geometry information from the modelling software and transfer it to the structural analysis FEM software automatically setting up and running the analysis then reverting the results back to the modelling software for optimisation. This interoperability is a key feature in a BIM workflow to prevent information loss and latency as well as quicken decision making (Gomes *et al.*, 2018).

The proposed framework emphasises the importance of communication between the architect and engineer throughout the process, to ensure that any potential problems are highlighted and dealt with timeously. The automation resolves some of the most tedious and repetitive tasks that are invariably a part of the design process so that architects and engineers can focus on conceptual design, engineering thinking and analyses of results. Nonetheless, the study is limited to the conceptual design stage only and it remains to be seen whether or how it would work in practise with other considerations such as formwork for construction of the shell structure (Gomes *et al.*, 2018).

This page is intentionally left blank

3. PARAMETRIC MODELLING AND COMPUTATIONAL DESIGN TOWARDS MODEL GENERATION

3.1. Introduction

Based on the Perpectum research proposal by Azenha (2019), this work proposes compression-only structures tessellated into precast panels cast on a flexible mould, with in-situ self-sensing prestressing cables. The panel size can be approximately 1m x 1m with ± 200 mm to enable easy lifting without complex machinery required. A thickness of 300mm is selected preliminarily to assess structural performance. As seen in the literature review presented in Chapter 2, the technological aspect and modular fabrication could be available with the current technology (refer to Figure 20).

Ideally, the prestressing cables employed in Perpectum, are low stress, non-metallic and cost-effective members made up of multiple layered and braided cables similar to those used in the marine industry. However, in this thesis, 20mm diameter steel cables are used to evaluate the validity of the proposed system. The construction system proposes sequential assembly of the concrete panels to maintain robustness during construction, similar to masonry construction (refer to Figure 11). Each concrete panel is prestressed in two directions as it is added to the structure to maintain stability. The idea is to have technology that allows the concrete panels to have external anchor heads for the post tensioning that are decoupled after stressing to allow the next concrete panel to be placed.

In the age of BIM, the integration of parametric modelling and computational design processes is becoming a fundamental part of the design process and so it is with the proposed construction system. Thus, the objectives of this section are to explain the use of parametric modelling and computational design processes to create the structural shape, thicken and tessellate the structure and add the cable geometry; assign an assembly sequence to each panel using cellular automata and generate the BIM model. A regular, simple geometry is used for the description of the processes to simplify and focus on the explanation of the procedures. However, it is possible to define more complex geometries provided they have width of at least 4m, at least four sides and either line or point supports. The structure's height depends on functional and architectural requirements.

The chapter starts with an explanation of the vault design system (Section 3.2) followed by a general overview of the design procedure (Section 3.3). This is followed by Section 3.4 that explicitly describes the step by step implementation of the algorithm for the design, including the procedure for obtaining the construction sequence using cellular automata principles. The chapter ends with a description of the connection from the model generation software to the BIM platform (Section 3.5).

3.2. Geometrical concept for vault system

A compression-only structural shape with supports on the ground or on walls can be achieved using parametric modelling and computation design from a form-finding process. Starting with an arbitrary planar geometry, it is possible to use point or line supports to constrain the shape - refer to Figure 22.




Figure 22 - Parameters and constraints for form-finding for a generic rectangular shape - Top view

Then, an upward load can be applied to the points restrained by lines with an assigned stiffness (springs), and through iterations to obtain static equilibrium and a compression-only structure.

Using the generic rectangular shape shown in Figure 22, the main concepts, parameters, and constraints essential for the form-finding process are explained as follows:

- 1) The length, a and width, b can be increased or decreased. In fact, the curves representing these lengths can be linear or curved.
- 2) The size of x and y can be changed by changing the number of divisions in any one of the directions, as required.
- 3) Consequently, this leads to changes in the lengths of the springs and positions of the nodes.
- 4) Any of the points can be selected as supports; any of the lines can be selected as support lines. The supports do not change position whilst all other points can shift once the load is applied.
- 5) The loads are applied on the points.
- 6) The lines are assigned a spring stiffness that can be adjusted as required.

Therefore, depending on the boundary conditions, an infinite number of structural forms is possible. As described in Chapter 2, the resulting structure can be divided into panels which can be post tensioned during construction to reduce the formwork required. The resulting structure from form-finding is more efficient in terms of the force distribution in the system.

3.3. Overview of parametric modelling and computational design workflow

This section describes the parametric modelling and computational design workflow. The form-finding and construction sequencing procedures of the project were carried out through the Visual Programming Language (VPL) Grasshopper 3D that is executed within the Rhinoceros 3D version 7 (Rhino) Computer-Aided Design (CAD) software.

There were three main reasons for this choice i) it has built-in add-ons to develop the form-finding processes such as Kangaroo and because ii) it allows the implementation of interoperability operations with a BIM platform (Revit or ArchiCAD). Various other approaches for form-finding can be used including DynaShape, an add-on of Dynamo – a VPL of Autodesk Revit or textual programming such as Python. However, the former was found to not be as robust as Kangaroo and it would have been more time-consuming to troubleshoot as there is currently less literature on it. Then the latter required more time for familiarisation but in theory would have interesting possibilities especially with the use of pyRevit, a Python based plug-in for Revit.

After the first stage of design generation in Rhino, a plug-in called “Rhino.Inside.Revit” was used for bi-directional interoperability between Rhino 7 and Autodesk Revit 2021, allowing users to model in the Rhino environment and have the full geometrical shape immediately available in Autodesk Revit for BIM purposes. Any changes in Rhino were instantaneously updated to Autodesk Revit, similar to how Dynamo works.

3.4. Implementation of the computational design model

This section describes the process by which the computational design model was defined and generated and connected to the BIM platform. The description includes the form-finding process using Kangaroo; followed by the conversion of the Kangaroo output from planar to solid and its subsequent tessellation to represent the panels; thereafter the procedure for cable curves generation is explained and followed by the cellular automata algorithm to define the assembly sequence; finally the connection procedure to the BIM platform is presented.

3.4.1. Structural equilibrium by form-finding

To generate geometries with compression-only structural behaviour, a form-finding algorithm was defined in Grasshopper 3D. The initial step in the implementation of the algorithm was using Kangaroo and its Dynamic Relaxation form-finding strategy, described in Chapter 2. Although Kangaroo was used in the study, it is possible to use other Grasshopper 3D plug-ins such as Karamba 3D or BullAnt created by Geometry Gym. However, the two are geared towards conducting the structural analysis in Grasshopper 3D which was not the intention in this case. In summary, the procedure is as follows: points are defined for a surface, from which a mesh or grid of points connected by lines are defined; then the lines are assigned a stiffness and loads are applied to each node on the grid; supports on the grid are defined and finally iterations occur to find static equilibrium.

Since the form-finding is achieved by the application of forces to a network of points connected by springs, the first stage consists in the definition of a network. Figure 23 illustrates the generative schema of a simple network of 7m by 5m with 1m subdivisions in each direction. The sizes of the divisions of the network were chosen to keep the resulting panels the same size as much as possible and in consideration of the space for the post tensioned cables. However, the size changes to $\pm 200\text{mm}$ more than 1m after the form-finding is carried out. The process begins with the definition of the points (Figure 23a) which are then used to form the lines (Figure 23b) which are in turn used to define the surface (Figure 23c).




Figure 23 - Generative Schema of a regular 7x5 network, top view and axonometric view

Depending on the desired shape, some of the “naked” points (points on the *boundary* of the mesh) were selected to be the support points (Figure 23d). In this case, the four corner points, 0 to 4 are the support points. These are the points that will remain in the same position when the form-finding is carried out. The “clothed” points (points *inside* the boundary of the mesh) connecting the lines of the mesh were assigned a vertical upward force (refer to Figure 23e) to move the points, find equilibrium and generate a shape. Thereafter, all the vertical and horizontal lines between the points of the mesh were assigned a spring stiffness that provides resistance to movement when the vertical force is applied (refer to Figure 23f).




Figure 24 - Grasshopper definition for the generation of a simple relaxed mesh through Kangaroo form-finding solver

Subsequently, as shown in Figure 24, under the INPUTS, the geometry (mesh), Force Objects (forces and springs), AnchorPoints (supports) and number of iterations were used as inputs to the Physics SOLVER “ZombieKangaroo” to perform the form-finding. The regular Kangaroo solver was not used to avoid having to reset and having the solver always running in the background, thereby using up memory, and taking up time. A fixed number of iterations was selected for the solver to come up with equilibrium based on the input parameters. When the solver is run, the OUTPUT from the solver (see Figure 24) is a 3-dimensional parabolic-shaped, dome-shaped or vault-shaped mesh. Varying the starting points, support locations, spring stiffness and vertical force results in different shapes as shown in Figure 25.




Figure 25 – Form-finding mesh results with 3 varying inputs, axonometric view

Initially, the use of genetic algorithms was considered in finding the optimal size of the panels or the U and V divisions. However, it was found that this was unnecessary as the solution was just a matter of a simple calculation for the simpler geometries in this work. But this would be useful for optimisation of the system in future.

3.4.2. Thickening, tessellating and discretisation of the structure

The next process was the creation of individual solid panels by thickening and tessellating the mesh output (see Figure 19). Grasshopper 3D has panelling tools options that could have been used to accomplish this task. Alternatively, Revit Adaptive Components were considered but the resulting individual panels were perpendicular to the surface. This resulted in angled separation at the interface and the intended smooth geometry is not maintained (see Figure 26). Although methods to overcome this are proposed in the literature (Hadilou, 2014) another procedure thought to be simpler was followed.






Figure 26 – 3D view of gaps between panels resulting non-smooth curve from using Panelling tools

The vault model illustrated in Figure 25c was considered as a case study for this chapter. As the first step, the mesh geometry is converted to a solid object. This was done by choosing a thickness (300mm in this case), and the vertices of the mesh were shifted up and down to form the top and bottom surface of the structure respectively. The U and V curves are used to split the surface into panels by obtaining the middle U/V line of the entire surface and dividing it into the desired number of panels and then using these curves to split/fragment the surface as shown in Figure 27.



a) Bottom surface b) Bottom surface fragmented c) Top surface fragmented

Figure 27 - Generative schema: Surface fragmentation, axonometric view



a) Bottom surface U/V Curves b) Top surface U/V Curves c) Top and bottom U/V Curve surfaces

Figure 28 - Generative Schema: U/V Curves for Top and Bottom Surface, axonometric view




Figure 29 – 3D structure segmented into panels and plan view with labelling

A final operation was conducted combining Figure 27b and c with Figure 28c to obtain the 3D structure segmented into panels as shown in Figure 29.

3.4.3. Generation of cable curves

Once the panels had been generated, the next procedure was defining the algorithm for generation of the cable curves in Grasshopper 3D. In the algorithm, cable curves representing the centre line of the post tensioned cables were defined for the transfer to the structural analysis software which requires curves to form the cables. Referring to a single panel as shown in Figure 30, the cable edge distances c and e are between a third and a quarter of the panel dimension l or m . As mentioned, the panel dimension l or m is at approximately 1m and the panel thickness is fixed at 300mm. The cable centre line is offset **down** from the panel centre by its radius for the cables in one direction and offset **up** by the same dimension in the other direction so that the cables do not clash.




Figure 30 - Panel and cable parameters and constraints

Using the same example as for the panels, the process for the generation of the cable curves was as follows. First, two separate surfaces were offset to the desired positions for the centre line of the cables in the U and V direction. Next, the central V line was selected and split into 3 times the number of specified V divisions.




Figure 31 - Creation and selection of cable curves in U direction, axonometric view

Thereafter, curves in the U direction were defined from these points to the edge of the surface (see Figure 31b). Following which, a pattern was used to separate the U curves on the edges of the panel from those which were within the panels as shown resulting in Figure 31c. After this procedure, an intersection component was executed using the edges/curves of the panels to obtain the cable curves per panel only in the U direction. The same procedure was repeated on the lower surface to get the cable curves in the other direction with U and V direction/curves swapped with results shown in Figure 32.




Figure 32 - Creation and selection of cable curves in V direction, axonometric view




Figure 33 – Top and Bottom cable curves in U direction and labelling for each panel




Figure 34 – Left and Right cable curves in V direction and labelling for each panel

The cable curves were further divided into four lists to separate the top and bottom (Figure 33) and, left and right cable curves (Figure 34) in each panel. The reason for this was to have labelling consistent with the labelling of the panels (see Figure 29). Figure 33 and Figure 34 depict the Top view of the example for easier visualisation. The panel in the left bottom corner is numbered “0” (see Figure 29) while the cables in the “0” panel will also be numbered “0” (refer to Figure 33 and Figure 34).

3.4.4. Creating the assembly sequence using a cellular automata algorithm

The panels and cables presented in the previous sections were assigned an assembly sequence. Controlling the assembly sequence of the panels means they can be brought onto site in the order in which they are needed thereby saving time and money. Additionally, it also allows designers to generate multiple solutions and consequently optimize the forces on the structure during construction. The assembly sequence algorithm in this study was defined using principles from cellular automata algorithms. The method was selected for automating the assembly sequence because it was successfully used previously for a similar application on dam construction sequences (Fernandes, 2015) and for its use of decision-making based on previous information. Generally, cellular automata algorithms make use of a network of *cells* and their *neighbours* to change the *status* of the cell i.e. dead or alive, alternatively active or inactive, depending on simple rules based on how many of its neighbours have the same status (Herr and Kvan, 2007). In this case, the cells were related to the panels and the status refers to whether the panel has been placed on the structure during construction.

The cellular automata algorithm was defined in Grasshopper 3D and run using the Anemone Plug-in which allows users to run loops. The *Loop Start* component has some input data which is then connected to and updated with data from the *Loop End* component. The user can specify the number of repetitions then use the reset button to run the loops. Once completed, the user can obtain the final data from the *Loop End* component as explained in Table 1 and illustrated in Figure 35.

Table 1 – Grasshopper Cellular automata algorithm task description

Task	Description
1. Inputs	The initial layout is defined and each cell is entered initially as “dead”. The number of iterations is set and the reset button is used to start the loop.
2. Loop Start	Received inputs and exchanges information with the Loop End.
3. Find Neighbours	Proximity component is used to find the number of neighbours based on the initial layout.
4. No. of live neighbours	Used to calculate how many neighbours that each cell has.
5. Separate dead/live cells	Sift component is used to separate the dead and live cells in each loop.
6. Dead cell test	Checks whether a particular cell is dead depending on how many live neighbouring cells it has.
7. Live cell test	Checks whether a particular cell is alive depending on how many live neighbouring cells it has and whether it was alive before.
8. Combine next gen. dead and live cells	Combines information from Task 6 and 7 and inputs back into the system.
9. Merge old and new information	Records information during each loop and enters that information back into the new loop.
10. Loop End	Data can be obtained after the number of iterations specified have been run




Figure 35 – Grasshopper cellular automata algorithm using the Anemone Plug-in

A lower number of neighbours was used for the purposes of this study to reduce and control the number of cells activated in each loop. The assembly sequence in this case requires connection with adjacent panels only and not corner cells for connection with the PT cables see Figure 5.

The cellular automata algorithm was carried out by first setting all the cells as “*dead*” by assigning them a value of *zero*. Then for the following generation, selected cells were set as “*alive*” by assigning them a value of *one*. For subsequent generations, the algorithm checked the current status i.e. dead or alive (zero or one), of each cell for that generation and then decided whether to change its status or keep it the same. This was done by first establishing a particular cell’s neighbours (see Figure 37) and then checking the value of each neighbour (zero or one).

Then the sum of the values of all neighbouring cells determined whether the cell in question would live (be assigned a value of one) or stay dead (value zero) in the subsequent generation. Dead cells only became alive once they were in the proximity of between one and three live cells. Once activated, live cells stayed alive for all subsequent generations. The activated (live) cells during each loop/run were recorded to form the assembly sequence.

Changing the assembly sequence leads to changes in the forces on the structure during construction. The sequence of activation and hence the assembly sequence can be changed by adjusting which cells are activated or set alive first. For instance, starting with all dead (*green*) cells (see Generation 0 in Figure 38a) then activating (*red*) the innermost bottom and top cells at either end i.e. Cells 1, 2 and 3; 31, 32 and 34, results in generation 2, 3 and 4 shown in Figure 38b, c and d, respectively:




Figure 38 - Cell automata activation sequence – inner panels activated first

This assembly sequence was then applied to the order of the panels and cables as seen in Figure 39.




Figure 39 - 3D and Plan View labelled with Assembly Sequence (1)

Alternatively, starting with all dead cells (Figure 40a) then activating the outermost live cells at the four corners i.e. Cells 0, 5, 4 and 9; 30, 25, 29 and 34, results in the sequence shown in Figure 40b), c) and d) as follows.




Figure 40 - Cell automata activation sequence – outer panels activated first

This assembly sequence was then applied to the order of the panels and cables as seen in Figure 41.




Figure 41 – Axonometric and Top View labelled with Assembly Sequence (2)

3.4.5. Connection and interoperability with BIM platform including level of information need

An important part of the workflow is the connection of the geometry to BIM platform. While ArchiCAD or Tekla are possible candidates, Revit was the BIM platform used in the study partly because the “Rhino.Inside.Revit” plug-in provides bi-directional interoperability between Rhino and Autodesk Revit. After the modelling stage, the geometry defined in Rhino was “baked” to Autodesk Revit geometry using the “Rhino.Inside.Revit” plug-in. The advantage of using it is that any changes that are made in Rhino can be immediately updated in Revit without the need to re-do any work. The results before and after baking are seen in Figure 42 and Figure 43 respectively.






Figure 42 - Rhino geometry in Revit before baking, axonometric view




a) Shaded graphic display with single panel displaced and highlighted




b) Wireframe graphic display to show cables

Figure 43 - Revit geometry low level of detail, axonometric view

Depending on the project phase and level of information need required, the geometry can be updated, and more information added to the model accordingly for the purposes of BIM. The cable curves would be sufficient for a lower level of detail but for a higher one, openings and the thickened cables would have to be represented. The operation can be carried out in Grasshopper and transmitted to Revit via the same procedure described earlier in this section. For the example presented in this section, the results are depicted in Figure 44.



a) Consistent Colors Visual Style with single panel displaced



b) Wireframe Visual Style showing cable thickness

Figure 44 - Revit geometry with higher level of detail, axonometric view

Metadata can also be added either using the Grasshopper interface Rhino.Inside.Revit plug-in or using the Revit interface to assign native Revit families, set materials etc.

Other tools such as Geometry Gym's Rhino-Revit IFC and Hummingbird can be used for converting Rhino geometry to Revit geometry. However, Hummingbird is only compatible with specific versions of Rhino and Revit and is not currently supported by the latest version of these programs. Similarly, Geometry Gym's IFC conversion procedure from Rhino to Revit requires a license and does not provide direct bidirectionality like the Rhino.Inside.Revit plug-in which accesses the Revit API. Nevertheless, Grevit, a free Grasshopper 3D Plug-in is just as effective as the Rhino.Inside.Revit plug-in and also allows a workflow suitable for BIM but the component exchanges are limited to certain Revit family types such as beams, columns and slabs.

3.5. 3D printing

The proposed construction system was assessed by 3D printing the blocks from the form-finding process described in this chapter (refer to Figure 45). Each block consisted of 4 openings, two in each direction, slightly offset from the centre to prevent them from clashing. A keystone was placed on the topmost blocks to accommodate the assembly sequence which started from the supports on either side of the structure to the keystone. The blocks were connected by elastic wire passing through the openings in place of the PT cables. Tensioning the blocks using the wires adjusts the structural shape into position as shown in Figure 46 and Figure 47



Figure 45 - 3D printed blocks before assembly



Figure 46 - 3D printed blocks after assembly - Front view




Figure 47 - 3D printed blocks after assembly – axonometric view

This page is intentionally left blank

4. STRUCTURAL ANALYSIS PROCEDURES

4.1. Introduction

BIM Model Uses such as structural analysis are usually conducted following the model generation process as described in Chapter 3. Structural design analysis using FEA is vital to determine the construction and performance viability of shell structures. Moreover, decisions on the building blocks of the design including the material types, material strengths and connection types are made at this stage. This information is then communicated to the relevant parties involved in the construction process.

The FEA described in Section 2.3.3 was carried out using DIANA FEA version 10.4 (herein after referred to as DIANA), a Finite Element Analysis software developed by TNO Building and Construction Research Institute in Delft, The Netherlands. Other software such as Autodesk Robot Structural Analysis have the advantage of having direct interoperability with Autodesk Revit. Moreover, other FEA software such as SAP2000, ABAQUS and ANSYS are often used in structural engineering. Nevertheless, DIANA FEA was selected for this study because of its: i) ability to perform phased analysis which is essential for the thesis; ii) incorporation of Python scripts allowing automation of what would otherwise be tedious and time consuming tasks if done manually; iii) license availability and abundance of tutorials for learning.

As described in Chapter 3, once the geometry is in the BIM platform Autodesk Revit 2021 (herein after referred to as Revit), a plug-in developed in C# programming language is used to automatically generate a Python script that converts the Revit geometry syntax into DIANA geometry syntax. This Python script is then run in DIANA to reproduce the model from Revit. The procedure described was followed because there is currently no direct interoperability between DIANA and architectural programs such as Revit/Rhino.

An additional Python script was implemented to automatically assign the material properties, support conditions and loading on the structure as well as set-up the phased analysis in DIANA. Finally, the structural analysis is carried out in DIANA to ensure the structural soundness of the final solution which will be discussed in Chapter 5.

This Chapter presents the structural analysis methodology. Section 4.2 presents the structural concept of the proposed construction system. Section 4.3 describes the interoperability tool defined to connect Revit to DIANA. Section 4.4 discusses the DIANA property assignment and phased analysis procedures. DIANA examples are presented in Section 4.5 and the interoperability tool employed to automate the phased analysis is described in Section 4.6.

4.2. Structural concept of the construction system

4.2.1. Panel size and material

The panel size can be approximately 1m x 1m with ± 200 mm to enable easy lifting without complex machinery required and a thickness of 300mm is selected, as mentioned in Chapter 3. The stresses are expected to be low and therefore low-strength concrete can be used to reduce the environmental impact

of this construction system. This might be achieved by investigating using concrete mixes with recycled materials. In this study, the C30/37 concrete grade is used as a first check for tensile strength. However, creep, shrinkage and thermal effects will not be considered and are beyond the scope of the thesis.

4.2.2. Post tensioning load

To estimate the load requirements at the interface, preliminary hand calculations were performed assuming a cantilever system with two tilted panels: one on top of the other with a PT load of 25kN. The expected stress at the interface between the panels is estimated with this PT load. In estimating the interface stresses between the top and bottom block, the first step consisted of drawing a free body diagram where a 3D global coordinate system (X,Y,Z) and a 2D local coordinate system (u,v) are used – refer to Figure 48.




Figure 48 – PT Block Free body diagram and stress interface calculations

The free body diagram of the top panel consists of the PT loading and the panel self-weight denoted as P_v and W_z respectively. The PT loads act along the v-axis parallel to the block, while the self-weight acts parallel to the Z-axis. In theory, the self-weight component along the v-axis (W_v) contributes to the perpendicular stress on the interface, while the component on the u-axis (W_u) would generate a bending moment at the interface between the two panels (Figure 48).

By introducing a PT loading of 25kN in each cable, compressive (negative) stress of 0.357 MPa and zero (positive) tension stress occur. Values less than 25kN would lead to the occurrence of tensile stresses at the interface. This would mean that the two panels are not in complete contact with each other. Therefore, a conservative PT Load of 40kN is used. This value is lower than the usual forces for commercial PT systems. Cable diameter of 20mm will be used which is close to the standard 18.7mm used for PT systems.

4.2.3. Temporary supports during construction

Ideally, the system would have no construction supports. However, preliminary studies suggested that tension stresses may arise if no provisional supports are provided. Therefore, a decision was made to add provisional supports e.g. made by a prop connected to a standard plate, which can be quickly sized and removed as required, with minimal increase, if any, to the construction cost.

4.3. Interoperability tool for connection between modelling platform and structural analysis software

Currently, few platforms allow direct interoperability between architectural and structural analysis software. Hence the most common *modus operandi* of structural analysis software is accessing the geometry using Industry Foundation Class (IFC), an object-oriented data exchange standard. Although, DIANA, has the capability of reading IFC syntax, ad-hoc programming was implemented to have more flexibility in customising the data exchange.

Solid geometry in both Revit and DIANA are made up of surfaces (faces) which are defined by a set of edges and vertices. Since the geometry from Revit obtained in Chapter 3 is made up of panels (solids), it is necessary to translate this information to DIANA geometry. This is done by customising a C# script designed by fellow Masters student (Correia, 2021) whose thesis will be submitted in September, 2021. The script accesses the Revit Application Programming Interface (API) and converts the Revit nomenclature to DIANA nomenclature. Then the script produces a Python script with syntax readable in the DIANA environment. The algorithm consists of the following steps i) identifying the panel and cable geometry from Revit ii) decomposing the Revit geometry into basic elements iii) composing the basic elements into DIANA geometry syntax iv) producing a Python script

In Revit syntax, the cable geometry is a curve and encompasses non-linear type lines. This is useful for this project where free form structures are generated. The Revit curves are tessellated and divided into segments. Then, the points forming these segments are combined to form DIANA curves (Correia, 2021) as illustrated in Figure 49.




Figure 49 - Summary of conversion process of cable curves from Revit to DIANA geometry

Similarly, the C# code uses the Revit API to obtain the panel geometry. More specifically, the algorithm first decomposes each panel which in Revit semantics are called “solids” into “faces” as illustrated in Figure 50. Afterwards, faces are decomposed into edges that are tessellated into points. The points from Revit by default are defined using the Imperial System (dimensions in inches) and therefore are converted to the Metric System (dimensions in meters) which is the default system in DIANA. Thereafter, these points are converted to DIANA curves which in turn are converted to wires. The wires

are then sewn together to form sheets. Finally, the sheets are combined to form a DIANA block that represents a panel.




Figure 50 - Summary of the conversion process of a single panel from Revit to DIANA geometry

4.4. DIANA FEA Property assignment and Phased Analysis procedures

4.4.1. Property assignment procedure

The first step in creating a new Project in DIANA is to define shapes that can be related to real world construction items. The detailed steps for the procedure are presented in Appendix 2. In this case, the shapes were created as described in Chapter 3 and read into DIANA using the interoperability tool presented in Section 4.3. Thereafter, the following DIANA steps, which will be discussed further, can be followed:

- i) Add materials and assign material characteristics
- ii) Assign shapes to geometry. Shapes can be assigned as either geometry or reinforcement
- iii) Assign a material to the shapes
- iv) Add loads to the shapes

When adding a new material to the project, DIANA allows the user to select whether it will be modelled as a Class and based on the Class chosen, the Material model can be chosen which means the results will be based on established international codes for instance the fib Model Code for Concrete Structures 2010 or Eurocode 2 EN 1992-1-2 for reinforcement.

For Concrete materials, the Class options are the “Concrete design codes” and “Concrete and masonry”. The “Concrete and masonry” was selected for this study so that the results are applicable to different codes. The material model selected was “Linear elastic isotropic” because the concrete would have the

same properties throughout and have linear elastic behaviour i.e. stress and strain are linear, and Hooke's law applies. Additionally, the materials are expected to recover after the application of loads to the structure.

Conversely, for the post tensioning cable reinforcing, "Reinforcements" or "Steel design codes" can be selected. Ideally, the goal would be to have post tensioning cables made from maritime cables but for the purposes of checking the viability of the construction system, steel properties were used. Once again, no code was selected and the more generic "Linear elasticity" behaviour was selected. However, the "Bonding" aspect was included to have the option to specify that the post tensioning cable is not bonded to the concrete. This means that the post tensioning cables and concrete can move independently of one another.

After the Material Class and Material model have been selected, the next step is to specify the aspects to be included. Aspects such as Creep, Shrinkage, Thermal effects, and Strength reduction can be included in the analysis. However, as mentioned before, none of this behaviour was modelled since the focus here is the framework, but these can be easily set up in DIANA. Thereafter, the Young's Modulus, Poisson's ratio and Mass density can be specified.

Once the materials have been defined, the "Element Class" type is selected to define the shape. "Structural solids" were selected as the Element class for the panels in the study. Structural solids are general purpose, allowing arbitrary loading and three-dimensional stress. The alternative would be "Rubber solids" used for rubber-like structures with hyper elasticity which is not applicable here. DIANA's default elements from structural solids are of type HX24L with 8 nodes and a 2x2x2 integration scheme. Further research would be required to investigate how a different element would affect the results.

The post tensioning cables in the DIANA model can be represented by assigning a load to the curves. The process requires firstly adding a new load case and then adding loads to the load case. Then, the "Load type" is selected as a "Post tensioning load". This load type can only be assigned to reinforcement therefore the curves representing the cables are set as "Reinforcement shapes" before being loaded with the Post tensioning load. Either end of the curve or both ends can be assigned as the "Anchor point" where the force is applied. In this case only one of the ends was selected as the anchor point to make it easier to automate the process. Finally, the "Nodal anchor force" in kN, "Coulomb friction coefficient" and "Wobble factor" values need to be specified in case of prestress losses.

4.4.2. DIANA Phased Analysis

The DIANA FEA program offers various analysis types, from Structural Linear Static to Structural Nonlinear and Structural Response Spectrum. The "Staged construction" analysis was selected for the purposes of this study to investigate how the structure responds to the gradual addition of precast structural panels and their post tensioning cables during construction. Each construction stage is added manually to the analysis as shown in Appendix 2. The number of stages equates to the number of blocks in the structure. Each stage is accumulative and equates to the previous block plus activation of a new block and its post tensioning cables. It is also worth noting that the post tensioning stress from the previous blocks are not destressed and then stressed again with a longer cable joining the old and new

cables. This was considered early on in the study but found to be overly complicated to enact in the model and in a real construction. However, it is worth looking into in the future should the technology be available.

4.5. DIANA Examples

4.5.1. Four-block model phased analysis

There are several steps that have to be repeated for each analysis stage. For example, DIANA staged analysis is usually used for geo-mechanical structures. Therefore, it is necessary to specify that there is no water present and de-select both the “Clear displacements at beginning of stage” and “Initialize stresses in new elements” options for each stage of the analysis (refer to Figure 52b). Additionally, for the loads, the self-weight is automatically included in each analysis stage. However, the post tensioning load must be added to each analysis stage.

To get familiar with the phased analysis in DIANA an example consisting of four panels with size 1m x 1m x 0.3m, angled at 60 degrees from the horizontal plane is hereafter presented. The step by step procedure for creating the geometry and setting up the analysis stages is presented in Appendix 2. The model is composed of four concrete panels each with four PT cables as shown in Figure 51.






Figure 51 – DIANA example with four panels - Isometric and right view


The PT cables ensure the connection and stability of the panels during construction. Each PT cable is related to the block it is in. For instance, all the cables in Block 4 are in a group called Cables 4 (Cable 4A, 4B, 4C and 4D as denoted in Figure 51). The construction consists of four stages, each one a single analysis stage in DIANA. The active parts for each of the four stages are shown as axonometric views and inputs in Figure 52 and Figure 53.




a) Stage 1 axonometric view



b) Stage 1 Active parts information



c) Stage 2 axonometric view




d) Stage 2 Active parts information


Figure 52 - DIANA Stages of construction 1 to 2 for four-panel example

In Construction Stage 1 (Figure 52a and b), Block 1 and all its corresponding cables (Cables 1) are added to start the assembly sequence. Then in Construction Stage 2 (Figure 52c and d), Block 2 and its corresponding cables (Cables 2) are also added to the system.


Afterwards, in Construction Stage 3 (Figure 53a and b), Block 3 and all its corresponding cables (Cables 3) are added to continue the assembly sequence. Finally in Construction Stage 4 (Figure 53and d), Block 4 and its corresponding cables (Cables 4) are also added to complete the construction of the four blocks. The PT cables ensures the connection and stability of the panels during construction.




a) Stage 3 axonometric view



b) Stage 3 Active parts information



c) Stage 4 axonometric view



d) Stage 4 Active parts information

Figure 53 - DIANA Stages of construction 3 to 4 for four-block example

As illustrated the process of manually adding a construction stage and activating each the blocks and cables is a laborious process. For this reason, an interoperability tool was designed to automatically perform the phased analysis with the assembly sequence related to the cellular automata algorithm.

4.5.2. Python scripting for DIANA

The DIANA FEA User's manual provides specific Python commands that are readable and executable by the DIANA API and can be used to automate certain tasks. Alternatively, the command console inside DIANA displays the Python commands for each action carried out in DIANA. For example, a

1m length, 1m height and 0.3m breadth block was defined and assigned the material concrete with Young's modulus 30 MPa and mass density of 2500kg/m³ as per Figure 54.




Figure 54 - DIANA single panel size 1m x 1m x 0.3m, axonometric view and properties

The resulting Python commands are shown in Figure 55.

```

Command console
> setModelAnalysisAspects( [ "STRUCT" ] )
> setModelDimension( "3D" )
> setDefaultMeshOrder( "LINEAR" )
> setDefaultMesherType( "HEXQUAD" )
> setUnit( "LENGTH", "MM" )
> setUnit( "FORCE", "N" )
> createBlock( "Block 1", [ 0, 0, 0 ], [ 1000, 300, 1000 ] )
> addMaterial( "Concrete", "CONCR", "LEI", [ ] )
> setParameter( MATERIAL, "Concrete", "LINEAR/ELASTI/YOUNG", 30000 )
> setParameter( MATERIAL, "Concrete", "LINEAR/ELASTI/POISON", 0.2 )
> setParameter( MATERIAL, "Concrete", "LINEAR/MASS/DENSIT", 2.5e-09 )
> setElementClassType( SHAPE, [ "Block 1" ], "STRSOL" )
> assignMaterial( "Concrete", SHAPE, [ "Block 1" ] )

```

Figure 55 - DIANA Example block properties and Python commands

Moreover, for any model that is created, DIANA automatically creates a Python script showing the commands that can be used to create/alter a model. From these options, Python's built-in capability to iterate and automate processes can be exploited through creating custom scripts to be run in DIANA.

4.6. Script for property assignment and construction phasing

A Python script was created that automatically assigns properties to the geometry as well as specifies the sequence for the proposed construction system. The Python script created from the C# program described in Section 4.3, is run in DIANA and the geometry from Revit is reproduced. For simpler geometry, it would be relatively quick to manually define and assign materials, loads, and supports and then set up an analysis. However, as illustrated in Section 4.4 and Appendix 2, the process is tedious and time-consuming for increased number of blocks with multiple construction phases. In order to speed up the structural analysis process and simplify making changes, further textual programming to

automate some of the *pre-processing* including defining the material, supports and loading properties and assigning them to the curves and blocks is carried out as part of this work (refer to Figure 56).

For instance, a script was created where the material “Concrete” is defined and assigned properties such as the compressive strength and then assigned to each block. Similarly, the material “Steel” is defined and assigned properties such as the Young’s Modulus of Elasticity and then assigned to each cable. The post tensioning load and the anchor positions is also assigned for each cable. By using textual programming, these values can easily be adjusted if required without too much difficulty. This is particularly useful in an AEC design environment where changes are bound to occur.

```
#Set units
setUnit( "LENGTH", "MM" )
setUnit( "FORCE", "N" )

#Create materials
addMaterial( "Concrete", "CONCR", "LEI", [ ] )
setParameter( "MATERIAL", "Concrete", "LINEAR/ELASTI/YOUNG", 30000 )
setParameter( "MATERIAL", "Concrete", "LINEAR/MASS/DENSIT", 2.5e-09 )
setParameter( "MATERIAL", "Concrete", "LINEAR/ELASTI/POISON", 0.2 )
addMaterial( "Steel", "REINFO", "LINEAR", [ "FRLGTH", "NOBOND" ] )
setParameter( "MATERIAL", "Steel", "LINEAR/ELASTI/YOUNG", 200000 )
setParameter( "MATERIAL", "Steel", "FREELE/FRLGTH", 1 )

#add Selfweight
addSet( "GEOMETRYLOADSET", "Dead load" )
createModelLoad( "Global Load 1", "Dead load" )

#add PT loads
addSet( "GEOMETRYLOADSET", "PT load" )
createBodyLoad( "PT load", "PT load" )
setParameter( "GEOMETRYLOAD", "PT load", "LODTYP", "POSTEN" )
setParameter( "GEOMETRYLOAD", "PT load", "POSTEN/TENTYP", "ONEEND" )
setParameter( "GEOMETRYLOAD", "PT load", "POSTEN/ONEEND/FORCE1", 40000 )
setParameter( "GEOMETRYLOAD", "PT load", "POSTEN/SHEAR", 0 )
```

Figure 56 – Part of Python script setting up properties

The last part of the Python script involves relating the cables to the blocks such that the cables would be activated when the corresponding block is activated in the assembly sequence. Because of the way the assembly sequence was set up in the Chapter 3, the numbering is in the order required and the desired cable can easily be recalled as needed. This is done using iterations and the “for” loop. A single analysis is defined consisting only of the first block in the assembly sequence and its cables. The following analysis duplicates the previous analysis with the difference that the next block in the specified sequence (see Section 3.4.4) is activated and so on until the last block and its cables have been added. The full Python script is available in Appendix 1.

5. FRAMEWORK DEFINITION AND CASE STUDY

5.1. Introduction

As part of a typical BIM process and generally required in a BIM Execution Plan (BEP), it is important to know who does what, when and how i.e. roles, timelines and responsibilities for each team member involved in the project. This ensures that before the project starts, each project stakeholder is informed of the scope of work, standards, modelling requirements, what is expected of them and the timeline for the deliverables. Another important aspect is the Data Exchange process between disciplines encompassing the software being used, how the information is transferred between them and the useability of the information (interoperability). It is important to be aware of all this information before the beginning of the project. This is where a process map or workflow comes in. In this chapter, a workflow with a case study is presented with the aim of representing how the compression-only shell design and structural analysis of the proposed construction system would occur in an actual project.

For the sake of simplification, the workflow is limited to a simple project where the client, an architect and a structural engineer are the only role players. It is assumed that there are no Mechanical, Electrical and Plumbing (MEP) requirements in the project and responsibilities such as detailing are performed by the architect rather than a draughtsperson. The starting point is a client brief describing the project requirements, which results in a completed BIM model with enough details to be handed over to the contractor for construction. Throughout the workflow, it is important that the structural engineering and architectural disciplines collaborate and provide continuous feedback to each other to prevent information latency. Similarly, the interoperability tools presented will prevent errors and information loss during the data exchanges.

Consequently, this chapter firstly presents a collaborative framework definition whereby the processes described in Chapters 3 and 4 are incorporated into a design workflow in Section 5.2. Section 5.3 presents the realisation of the parametric design and structural analysis of a free-form compression-only shell structure based on the framework. Finally, further applications of the framework are presented in Section 5.4.

5.2. Framework for workflow with architect and structural engineer

Preliminary concept sketches of the shell structure by the architect can be turned into a viable constructable structural shape through analysis and design performed by the structural engineer. The following is a presentation of a practical methodology or framework encompassing the work as described in Chapters 3 and 4 for how the actual processes and workflow can be achieved.

The framework used for the case study in this chapter is shown in Figure 57. The figure makes use of Business Process Model and Notation (BPMN) and is inspired by the work of Gomes (2018) to describe the workflow for a compression-only form-finding design and structural analysis of the construction system. The main themes of Processes 1, 2 and 3 are the Geometry Definition, BIM modelling and Structural Analysis respectively. Each of the processes are presented in greater detail forthwith.




Figure 57 – Framework for case study workflow

A zoom in of the first process i.e. Geometry Definition is shown in Figure 58. This is the most important process as its implementation affects the downstream processes.




Figure 58 - Process 1: Geometry definition

Initially, it requires the architect to obtain a brief from the client and produce the project scope (Process 1a) and preliminary concept sketch (Process 1b). Process 1b specifies Revit as the software of choice but since the sketch is only for discussion purposes, any suitable software can be used. This information is shared with the engineer (Process 1c) who then defines the preliminary parametric model by using Grasshopper 3D and performs form-finding in Kangaroo (Process 1d). Process 1 concludes with an agreed upon structural shape in Rhino and Revit (Process 1h) which relies on the collaborative effort from both the structural engineer and the architect (Process 1e-g). Due to the Rhino.Inside.Revit plug in, the Rhino geometric shape is then immediately available in Revit (Process 1h).

A zoomed in version of the BIM process is depicted in Figure 59. This process serves as the starting point for the construction model which is finalised in the third process.




Figure 59 - Process 2: BIM

The process involves the development of the Revit model by the architect (Process 2a) including defining the non-geometrical information and increasing the level of detail where required. This is based on information provided by the structural engineer and the project requirements (Process 2b). The result of Process 2 is a preliminary 3D BIM model in Revit (Process 2c).

Finally, a zoomed in version of the third process namely Structural Analysis is shown in Figure 60. The function of this process is to evaluate the construction viability of the geometry defined in Process 2 with the proposed construction system.




Figure 60 - Process 3: Structural Analysis

The process makes use of the Revit model from Process 2c and the custom interoperable tools described in Chapter 4 (Process 3a) to recreate the geometry for the structural analysis (Process 3b). If only minor changes are required to the model, they are communicated to the architect (Process 3d) who produces the final BIM model to be used for construction (Process 3e). Otherwise, there would be a need to return to Process 1. The framework is flexible and adaptable hence the engineer is also free to amend the model if required such as changing support conditions including adding temporary supports or other loads during Process 3b.

5.3. Case study of a new sustainable compression-only structural block construction system

A case study is carried out to assess the theory and the proposed framework. The idea is to use the framework to create a compression-only structural shape from form-finding and assess the structural viability of the proposed construction system as mentioned before. An outdoor shading space at Parque da Cidade, in Guimarães, Portugal is proposed, similar to the one in Venice (Figure 11). The shell is expected to experience wind and snow loading. Preliminary sketches from the architect produce the Revit rendering in Figure 61 as a result of the client brief (Process 1c in Figure 58).




Figure 61 – Preliminary sketch of Case Study from Process 1c

5.3.1. Parametric modelling

Parametric modelling and computational design as described in Chapter 3, are conducted as part of Process 1. The starting surface is made up of two parallel long curves joined to two parallel short curves as shown in Figure 62. As explained in Section 3.4.1, support positions are chosen to be along the two short curves, then the surface is divided into springs and nodes where the force is applied – refer to Figure 63a and Figure 63b respectively.




Figure 62 – Case study starting curves and resulting surface – Top view




Figure 63 – Case study support locations, springs, and force application positions – Top view

For the case study, a network of 14x10 cells is chosen so that the resulting panels are approximately of size 1m by 1m. The form-finding and tessellation process results in the mesh (Figure 64a) and solid panels with a thickening of 300mm (Figure 64b).




Figure 64 – Case study mesh and tessellated 300mm thick 3D shape – axonometric view

The cellular automata algorithm selected starts with the bottom middle cells at either end of the geometry and then moves progressively outward and upward similar to what is presented in Figure 38. On the one hand, in the initial order in Figure 65, the first block is in the bottom left corner and the assembly sequence goes from left to right (Arrow X) then up each row (Arrow Y) and left to right again until the final block.

On the other hand, in the final order in Figure 66, Cell 0 is at the bottom middle of the plan view while Cell 1 is at the other end. The neighbouring cells are activated sequentially from the direction of Arrows A and B to Arrows C and D and then to Arrows E and F until the top of the structure. This shows the power of the cellular automata algorithm as there is better control of the system and multiple directions can be activated, thereby speeding up the construction process.




Figure 65 - Case study initial order BEFORE cellular automata algorithm – Top view




Figure 66 - Case study final order AFTER cellular automata algorithm – Top view

Following the completion of Process 1, the result in Revit is shown in Figure 67. This occurs after the activities described in Process 2 of the framework.




Figure 67 - Case study – Revit model and cutout showing PT cables, axonometric view

5.3.2. Structural description: supports, material properties and loading

After the connection to Revit, the interoperability tool discussed in Chapter 4 is used to link the geometry and set up the analysis in DIANA and begin Process 3. As explained in Chapter 4, the geometry is automatically transferred from Revit to DIANA using a Python script, negating the need to re-define it. Some screenshots of the script running in DIANA are shown in Figure 68. Note that this sequence is the same as the one from Process 1 referred to in Figure 66.




Figure 68 - Case study - Screenshots of 6 assembly stages while Python script is running in DIANA

Once the geometry is added to the DIANA program, the next step is to assign the Boundary conditions, material properties loading and analysis for the FEA.

5.3.2.1. Boundary conditions

With the selected assembly sequence, the permanent supports (Figure 69) and the construction (temporary) supports are placed on the inner boundary of the structure as shown in Figure 70.




Figure 69 – Bottom view and axonometric view of structure with permanent supports




Figure 70 - Bottom view showing permanent and temporary construction supports

Each support point as shown in Figure 70 can correspond to a support plate and each corner of the panel can then be supported on the support plate. This was the direction taken in the study for ease of modelling but perhaps having support plates at the centre of the corresponding panels would be easier to set up on site. Although, adding supports can also be automated, in this case it was thought to be easier to add the supports manually since automation involved creating the algorithm for the supports based on the coordinates of one of the blocks.

5.3.2.2. Material properties

The material properties are automatically added to the DIANA geometry using the tool described in Chapter 4, as follows.

Table 2 - Case study - Material properties of concrete and steel

Material	Young's Modulus (GPa)	Poisson's ratio	Mass density (kg/m ³)	f _{yk} (MPa)	f _{ck} (MPa)	Partial safety factor (γ)
Concrete	30	0.2	2500		30	1.5
Steel	200	0.3	7700	450		1.15

The blocks are assigned the concrete material properties while the post tensioning (PT) cables are assigned the steel material properties. The PT cables have an anchor force of 40kN applied, as discussed in Chapter 4, with zero wobble factor and zero Coulomb friction coefficient with the assumption that prestress losses are low and have been taken into account in the 40kN.

5.3.2.3. Loads

The only load during construction is the self-weight. The wind and snow loads are checked after construction once the temporary supports have been removed. The wind load coefficient for this type of curved structure is calculated to the Eurocode code EN 1991-1-4:2005 Clause 7.2.8. For curved roof structures, the wind load coefficient is divided into three regions as shown in Figure 71 with A, B and C referring to Upwind slop, Flat top and Downwind slope respectively.




Figure 71 - Wind Load regions for curved roofs according to EN 1991-1-4:2005




Figure 72 - Wind values and direction as applied in DIANA

For a peak pressure of 1.56kPa and considering the wind loading coefficients results (A = 0.7, B = -1.1, C = -0.4) in the values shown in Figure 72. Applying the wind load assists in assessing how the structure would respond to a non-uniform load.

A uniform snow load is also applied based on an estimated snow load of 2kPa as presented in Figure 73, assuming a persistent situation and non-drifted snow. The point of this is to assess how the structure responds to an increase in a uniform gravity load.




Figure 73 – Uniform Snow load added to structure in DIANA

5.3.2.4. Load combinations

The structure was checked for the load combinations shown in Table 3 based on the Eurocode with a load combination factor of 1 being used for the self-weight as the focus is on the variable loads wind and snow (load combination 1.5). All losses are assumed to already be accounted for and so the load combination for the PT load is also 1. Additional load combinations can be considered in future.

Table 3 - Load combinations

Combination	Description	Type
C1	1.0*Self-weight + 1.0*PT Load	Serviceability limit state
C2	1.0*Self-weight + 1.0*PT Load + 1.5*Wind load	Ultimate limit state
C3	1.0*Self-weight + 1.0*PT Load + 1.5*Snow load	Ultimate limit state

5.3.2.5. Construction scenarios considered

Once the geometry, boundary conditions, loads and material properties and have been defined, the next step is to set up the analysis. Since there are 140 blocks, 140 stages are added for the staged construction analysis in DIANA with the first stage being the addition of the first block and Stage 140 representing the addition of the final block. Thereafter, the structural analysis is carried out as follows.

The five checks performed to investigate the structure response to the construction sequence and loading with the self-weight included in all cases are presented in Table 4. The purpose of the first check is a general stability and baseline check of the structure. Neither construction phasing, temporary construction supports nor loads other than the self-weight of the structure are considered. The rest of the checks all take into consideration the construction phasing. Check 2 considers construction phasing but not construction supports. Checks 3, 4 and 5 consider the use of temporary supports during construction.

Table 4 – Construction scenarios

No.	Description	Self-weight	Wind Load	Snow Load	Construction Phasing	Construction supports
1	Self-weight (SW) only	Yes	No	No	No	No
2	SW + Construction Phasing (CP)	Yes	No	No	Yes	No
3	SW + CP + Temp. Supports (TS)	Yes	No	No	Yes	Yes
4	SW + CP + TS + Wind	Yes	Yes	No	Yes	Yes
5	SW + CP + TS + Snow	Yes	No	Yes	Yes	Yes

The construction supports are removed after the final block has been added (Stage 141). Thereafter, two stages are added for the wind (Stage 142) and snow load (Stage 143). The first three checks are during construction and therefore are restricted to load combination C1 with only the self-weight and the PT load applied. The last two checks are preliminary Ultimate Limit State checks for load combinations C2 and C3 with wind and snow respectively.

5.3.3. FEA modelling and analysis

In the FEA conducted (see Section 4.4), the structural materials are assumed to be linearly elastic and a staged construction analysis is performed. Equilibrium should be maintained, throughout the construction stages. A simplified model is being used rather than having anchor plates for the prestressing cables or interface elements to observe the stresses between the panels. However, there should be no tensile stresses at the interfaces to guarantee construction stability. With more sophisticated models (e.g. with interface elements added), tension could be acceptable if it is small and the equilibrium is maintained. Consequently, the results will focus on the tensile stresses and two checks will be performed. Firstly, whether the stresses will lead to concrete cracking and secondly whether the interface stresses will cause instability and loss of equilibrium during construction.

According to the Eurocode 2 (EN 1992-1-1:2004, Design of concrete structures - Part 1-1: General rules and rules for buildings), given a concrete grade C30/37 the characteristic cylinder compressive strength is 30 MPa. For a fractile of 5%, the design tensile strength can be estimated as in Equation 1.

$$f_{ctd, 0.05} = 0.7 \times 0.30 \times \frac{f_{ck}^{2/3}}{\gamma} = 1.35 \text{ MPa} \quad \text{Equation 1}$$

A quadrilateral mesh of size 75 mm was selected to reduce computational time. Although a smaller mesh size can be used, the results were judged to be sufficiently close to those of the smaller 50mm mesh using a small model. The mesh can be further refined in future to investigate these preliminary results.

5.3.4. Results for Check 1: Self-weight only, no construction support and no phasing

The principal stresses S1 for self-weight of the structure only and no construction supports or phasing are displayed in Figure 74. The maximum tensile stress is 0.004 MPa and the maximum compressive stress is 0.046 MPa. Although not plotted here for the sake of brevity, Principal Stresses S2 and S3 are in the range -0.447 MPa to 0 MPa and the deflections are less than 0.05mm in all directions.

The results are to be expected based on the optimised nature of the structure. However, this system would require extensive construction supports that would significantly increase the project cost as

discussed in Chapter 2. Therefore, the proposed construction system is investigated including construction phasing, supports and loading in the following Sections with Checks 2 to 5 (see Table 4).




Figure 74 - Principal Stresses S1 - Self-weight only, no construction supports or phasing

5.3.5. Results for Check 2: Construction phasing but no construction supports

The next check is with the self-weight and construction phasing but with no construction supports. The assembly sequence from the cellular automata is used to consider the effect of adding one panel at a time. The tension stresses on the structure increase as the number of blocks in the system increase. It is highest at the top surface, gradually decreasing with depth to the bottom surface. The maximum tensile stress is 2.04 MPa at construction Stage 140, in the region where assembly commences (Figure 75).




Figure 75 - Principal Stresses S1 for Construction Stage 140 with no provisional supports

The stresses on the structure appear as soon as a block is added and are therefore caused by both the construction sequence as well as the post tensioning in the added block. Although, there is tension on both the bottom and top surfaces of the blocks, the tension is higher on the top surface as would be expected for this type of structure. The highest tension is for principal stresses S1. Although, the stresses are still generally less than 0.1 MPa, there is more tension in the structure with the introduction of construction phasing than before (Figure 74) and some areas of tension are greater than 1.35 MPa and will likely cause cracking. Therefore, it is necessary to add provisional construction supports to the system.

5.3.6. Results for Check 3: Construction phasing and construction supports

The third check is for load combination C1, with construction supports, and construction phasing added. This is the most important check as it evaluates how the structure behaves during construction of the proposed system. The construction supports are added along the middle centre of the structure as shown in Figure 70 and the structure is checked for possibility of cracking, interface stresses, deflections and bending moments.

5.3.6.1. Possibility of cracks during construction

This check is to determine if the tension on the structure is enough to cause cracks i.e. are the tensions greater than the design tensile strength of 1.35 MPa? With the use of construction supports, there is a reduction in tension throughout the construction phases as seen in Figure 76 compared to Figure 75. Parts of the system are in compression, but most parts are in tension. From the early stages of the construction (Figure 76), the tension in the system is at a maximum of 0.41 MPa. The tension increases steadily with the addition of each block until the tension is at a maximum of 0.78 MPa in Stage 140 (Figure 77) as opposed to the Check 2 where it was more than twice as high at 2 MPa.




Figure 76 – Principal Stresses S1 for Check 3 during early construction (1)




Figure 77 – Principal Stresses S1 for Check 3 during construction (2)

The maximum tension is generally less than 0.34 MPa in most areas from Construction Stage 1 to Stage 140 when the last panel is placed. However, there are points in the centre of the system at the corners of the panels that have higher tension (> 0.68 MPa) that are due to the provisional supports and in the regions where the cable anchors would be - anchor plates were not added to make the model lighter (Figure 77). These tensions will not be transmitted to the structure and will be taken up by the provisional support system and anchor plates. Nonetheless, it is evident that the tensions on the structure will not cause cracking as they are less than 1.35 MPa.

5.3.6.2. Possibility of instability due to interface tensions during construction

The interface refers to the surface-to-surface connection between panels (refer to Section 4.2.2). This is to evaluate the stability in the structure during construction and check the validity of the model. Since the structure is symmetric in two directions, the stresses will be similar for each half of the structure. The interface principal stresses S1 during Construction Stage 140 are shown in Figure 79 and Figure 80 with the former showing the long side and the latter showing the short side of the centre of the structure. In both cases, the level of tension increases steadily from outward to inward blocks of the slice. (In the construction sequence, the inner blocks were added first and therefore have higher tensile stresses).

In reference to Figure 79 and Figure 80, generally, the outer block stresses are more than 90 percent less than 0.15 MPa. In the middle blocks, although they are less than ten percent of the cross-sectional area, the regions of tension with higher stresses increase to between 0.15 MPa and 0.29 MPa. Similarly, on the top blocks, less than ten percent of the area have tensions greater than 0.29 MPa.




Figure 78 – Central Interface stresses during Construction Stage 140 (1)




Figure 79 – Central Interface stresses during Construction Stage 140 (2)




Figure 80 – Block A Interface stresses at Construction Stage 140

Overall, the interfaces have parts in compression and parts in tension during Construction Stage 140 as shown in Figure 78 and Figure 79. The tensile stresses along the vertical Block A (refer to Figure 78), are further illustrated in Figure 80 to demonstrate the tension force calculation procedure. Eighty percent of the interface area has tension of 0.15 MPa or less, while 5% has tension of 0.29 MPa or less and another 5% of the area has 0.44 MPa of tension.

The most critical interface areas for other construction stages were selected by inspection. The interface surface area is approximately $A = 1.1 \text{ m} * 0.3 \text{ m} = 0.33 \text{ m}^2$. The tensile forces at the interfaces for the construction Stages 97, 106, 132, 135 and 140 are as shown in Table 5.

Table 5 - Interface tensile stresses and forces at 5 Construction Stages

Stage	Tensile stress (MPa)	Area Percentage (%)	$F_i = \sigma * A * \%$ (kN)	Total Tensile Force F (kN)
97	0.12	90	35.64	43.89
	0.25	10	8.25	
106	0.12	50	19.8	19.8
132	0.16	50	26.4	46.4
	0.3	10	9.9	
	0.6	5	10	
135	0.16	90	47.52	57.42
	0.3	10	9.9	
140	0.44	5	7.3	51.7
	0.29	5	4.8	
	0.15	80	39.6	

For Construction Stage 97 which occurs after the two parts of the structure have been connected, more than 90% of the interface area are in tension with tensile stresses of 0.12 MPa or less and 10% of the interface area having regions of tension greater than 0.25 MPa. As more panels are added in Construction stage 106, the area of tension is 50% with tensile stresses of 0.12 MPa or less while the rest of the interface is in compression. For the later construction stages 132 and 135, about 50 to 90 % of the interface areas are in tension of 0.16 MPa or less. Less than 10% of the interface area have tensions exceeding 0.3 MPa. The rest of the regions (about 40%) are in compression.

To summarise this section, multiplying the tension stresses and their percentage of area on the interface gives the tensile force at the given interface for that construction stage. Generally, the tensile forces at the interface increase with increase in construction stage. The highest tensile force occurs at construction stage 135 with an approximate value of 58 kN. This is less than the force provided by the PT cables ($2 * 40 \text{ kN} = 80 \text{ kN}$) at each interface. Therefore, the PT cables provide a counter force that is more than the tension at the interface and so no loss of equilibrium would be expected during construction.

5.3.6.3. Deflections and Bending moments

The deflections were checked and found to be steadily increasing during construction but remained less than 0.5mm in all directions and all construction stages. A quick calculation based on the stresses and moment of inertia of the cross section ($M = \sigma \times I / y$) suggest that the bending moment is less than 5 kNm. This is well below the moment capacity (M_{un}) of a 300mm thick unreinforced C30/37 slab as per the calculation results of Equations 2 and 3.

$$f_{ctd, fl} = f_{ctm} \times \left(1.6 - \frac{h}{1000}\right) / \gamma \quad \text{Equation 2}$$

$$M_{un} = f_{ctd, fl} \times \left(\frac{h^2}{6}\right) \quad \text{Equation 3}$$

Mean axial tensile strength;	f_{ctm}	=	2.9	MPa
Design flexural tensile strength of concrete;	$f'_{ctd, fl}$	=	2.51	MPa
Moment capacity per m of unreinforced slab;	M_{un}	=	38	kNm

5.3.7. Results for Check 4: Wind Load

The fourth check is for load combination C2, which considers wind loading after construction. The principal stresses for S1 and S2 of the overall structure for this check are displayed in Figure 81 and Figure 82 respectively. Note that this is after the removal of the temporary construction supports.




Figure 81 – Principal stresses S1 for Wind Load after construction




Figure 82 - Principal stresses S2 for Wind Load after construction

The tensile stresses S1 (Figure 81) and S2 (Figure 82) are less than 0.34 MPa except in regions of the temporary supports where they are higher (0.67 MPa). This is much less than the design tensile stress of 1.35 MPa showing the unlikelihood of the structure cracking due to the loading. Principal stresses S3 for Check 4 are all in compression and between -2.14 MPa and -0.0 MPa.

5.3.8. Results for Check 5: Snow load

The fifth check is for load combination C3, which considers snow loading after construction. The principal stresses of the overall structure for this check are displayed for S1 and S2 in Figure 83 and Figure 84 respectively. Note that this is after the removal of the temporary construction supports as well.




Figure 83 – Principal stresses S1 for Snow Load after construction




Figure 84 - Principal stresses S2 for Snow Load after construction

Similar to the wind load results, the tensile stresses $S1$ (Figure 83) and $S2$ (Figure 84) are less than 0.34 MPa except in regions of the temporary supports where they are higher (0.67 MPa). This is much less than the design tensile stress of 1.35 MPa so it is unlikely that the structure will crack due to the loading. Principal stresses $S3$ for Check 5 are all in compression and between -2.15 MPa and -0.05 MPa.

5.3.9. Photo montage of case study

The photo montage shown in Figure 85 can be a real-life application of the case study presented in this chapter. The construction system is visible with the approximately 1 m x 1 m x 0.3 m concrete panels joined by PT cables in each direction. This illustrates the aesthetically pleasing aspect of the construction system.



Figure 85 - Photo montage of case study, Parque da Cidade, Guimarães

5.4. Other applications of framework

Three further structural shapes are presented to illustrate the versatility and variety of structural shapes that can be produced using the framework described in this chapter.

5.4.1. Exhibit A

The first application (Exhibit A), results in an igloo-like structure (refer to Figure 86). Referring to Process 1, starting with an arbitrary planar surface and selecting some supports, the form-finding method can be carried out. The cables can then be added to the structure corresponding to the appropriate panel using the cellular automata algorithm and then the structure can be tessellated and thickened as desired (refer to Figure 86c and d).




Figure 86 – Exhibit A: Rhino 3D results

Additionally, Process 2 of the framework i.e. the BIM modelling, and Process 3, i.e. the structural analysis processes can also be carried out. The models in their respective software programs are shown in Figure 87 and Figure 88 respectively.




Figure 87 - Exhibit A: Autodesk Revit result – 3D model




Figure 88 - Exhibit A: DIANA result – 3D model

5.4.2. Exhibit B

In the same way, Exhibit B can also be produced. With an initially four-sided surface and selecting the four corners as supports, the framework results from the parametric modelling and computational design (Figure 89), BIM (Figure 90) and structural analysis (Figure 91) procedures are shown.




Figure 89 - Exhibit B: Rhino 3D result




Figure 90 - Exhibit B: Autodesk Revit Result




Figure 91 - Exhibit B: DIANA model

5.4.3. Exhibit C and Photo Montage

Another application would be a shading structure also at Parque da Cidade, in Guimarães, Portugal (refer to Figure 92 to Figure 96). The structure would provide all the features proposed in the thesis. For instance, an integrated approach through the collaborative BIM-based workflow proposed herein would be used to design it saving time and cost. During construction, it would be largely self-supporting, and the cellular automata algorithm could be used to automate and optimise the construction assembly procedure. And finally, it would be durable and long lasting due to the use of maritime cables as opposed to steel reinforcement.




Figure 92 - Exhibit C: Panels in Rhino

Perspective ▾




Figure 93 - Exhibit C: Cables in Rhino




Figure 94 - Exhibit C: Revit model with two panels removed to show cables




Figure 95 - Exhibit C: DIANA model



Figure 96 - Photo montage of Exhibit C - application of the framework

This page is intentionally left blank

6. CONCLUSION

This work presented a collaborative BIM-based framework for a new sustainable compression-only structural block construction system. The introduction also included a description of the Perpectum concept (Azenha, 2019) which had been theorized in 2019, but never really implemented. It was followed by a literature review of sustainability and optimisation in construction and how this relates to shell structures and their sustainable design, including their incorporation into BIM processes.

Subsequently, there was a description of the parametric modelling and computational design processes that were carried out. A simple geometry was used to explain the procedures, including the one for obtaining the construction sequence using customised cellular automata principles and a description of the connection tool from the CAD to BIM platform. Next, the interoperability tools defined for structural analysis connection with the BIM platform and the one for automating the construction phasing were described. Finally, there was a description of the proposed framework for collaborative BIM-based workflows for the compression-only structural block construction system.

A case study was used to perform the procedures proposed in the framework including carrying out the computational design and form-finding (Process 1), producing the BIM model (Process 2) and carrying out FEA (Process 3). With the 3D printing of the case study, Technology Readiness Level (TRL) 2 and 3 could be said to have been achieved, with the technological concept formulated, and an experimental proof of concept provided.

The results based on the objectives in the introduction are as follows:

- Using the visual programming software Grasshopper 3D in Rhino 3D, simplified Process 1. An understanding of the list system and nomenclature of the Rhino 3D platform is necessary to optimise the process. The “Food for Rhino” plug-ins can be used to further assist in carrying out the tasks required such as the form-finding (Kangaroo) and cellular automata algorithm (Anemone). Once the program has been set up, only minor adjustments are required to quickly make changes due to the parametric nature of the model.
- In Process 2, Rhino.Inside.Revit provided direct interoperability from Rhino 3D to Autodesk Revit. Due to the requirements of the structural analysis software, it was necessary to first have the cables as lines. Thereafter, further computational modelling could be carried out to add openings and have the cable lines thickened for BIM modelling purposes. After that, metadata can be added to the model as required.
- An interoperability tool was used which accessed the Autodesk Revit API via C# for Process 3. It automated the creation of a Python script that transformed the geometry from Revit nomenclature to structural analysis software DIANA nomenclature. Then, another Python script was created which automated the materials property assignment and construction phasing analysis in DIANA.

- The structural analysis was performed for models with no construction supports, with construction supports, once the construction supports are removed and with wind, then with snow loading. The results show that:
 - i) It is challenging to erect a precast structure without it having excessive tensile stresses likely to cause cracking, unless there are some provisional construction supports. But with the proposed construction system, very few supports are required when compared to the normal construction of a shell structure and more importantly, no in-situ complex formwork is necessary.
 - ii) The construction sequence influences the tensile stresses that develop on the structure; hence the careful analysis of different scenarios is important.
 - iii) The construction system results in tensile and compressive stresses generally less than 0.5 MPa meaning material mechanical property requirements are minimal, raising the possibility of using recycled material for concrete.
 - iv) Tensile stress regions at the interface resulted in tensile force of up to 58 kN which is less than 75% of the applied PT load (combined 80 kN). Therefore, the structure is stable during construction.
 - v) Adding non-symmetric loads onto the structure did not result in adverse effects and only slightly increase (<0.01 MPa) the total stresses on the structure. It is a structure with much higher tolerance to unpredicted loads than standard thin shells.

It was also shown that the framework works for varying shapes and sizes and therefore can be used for a variety of structures and applications. For further work, more disciplines could be included in the framework such as the mechanical engineer and contractor. In addition, a more in depth look at the BIM modelling in Process 2 can be investigated including preparation of the documents for construction and how these would be linked to a factory for modular construction.

Additionally, it would be prudent to include earthquake loading as well as more load combinations to test robustness of the structural shapes produced. Although the resulting stresses at the interfaces were relatively low, there were not expected at all due to the addition of the prestress. For this reason, further investigation into the connection or interface between panels would be required to ensure stability. Moreover, it would also be worth investigating if increasing the number of cables in each direction may reduce the tension at the interface. Furthermore, there is the need for technological developments to make the proposed system really viable especially related to the challenges in terms of the moulds and cable positioning in the prefabrication plant.

REFERENCES

- Abdelmageed, S. and Zayed, T. (2020) ‘A study of literature in modular integrated construction - Critical review and future directions’, *Journal of Cleaner Production*, 277, p. 124044. doi: 10.1016/j.jclepro.2020.124044.
- Adriaenssens, S. *et al.* (2014) *Shell structures for architecture: Form finding and optimization*, *Shell Structures for Architecture: Form Finding and Optimization*. doi: 10.4324/9781315849270.
- Akbarzadeh, M., Van Mele, T. and Block, P. (2014) ‘Compression-only Form finding through Finite Subdivision of the Force Polygon’, in Brasil, Reyolando, M. L. R. . and Pauletti, R. M. O. (eds) *Proceedings of the IASS-SLTE 2014 Symposium: “Shells, Membranes and Spatial Structures: Footprints”*. Brasilia.
- Alexander, M. G. and Nganga, G. (2014) ‘Reinforced concrete durability: some recent developments in performance-based approaches’, *Journal of Sustainable Cement-Based Materials*, 3(1), pp. 1–12. doi: 10.1080/21650373.2013.876372.
- Azenha, M. (2019) ‘Horizon 2020 Excellent Science (Call for proposals for ERC Consolidator Grant) Topic : ERC-2019-COG Type of action : ERC-COG Call : ERC-2019-COG Proposal number : 864027 Proposal acronym : Brillouin4Life Deadline Id : ERC-2019-COG Table of contents’. Braga, pp. 1–52.
- Bao, Y. and Li, V. C. (2020) ‘Feasibility study of lego-inspired construction with bendable concrete’, *Automation in Construction*, 113(September 2019), p. 103161. doi: 10.1016/j.autcon.2020.103161.
- Barbosa, F. *et al.* (2017) *Reinventing Construction: A Route To Higher Productivity*, *McKinsey’s Capital Projects and Infrastructure Practice*. Available at: <http://www.mckinsey.com/industries/capital-projects-and-infrastructure/our-insights/reinventing-construction-through-a-productivity-revolution>.
- Bathe, K.-J. (2010) ‘RES.2-002 Finite Element Procedures for Solids and Structures. Spring 2010’. Massachusetts Institute of Technology: MIT OpenCourseWare, <https://ocw.mit.edu>. Available at: <https://ocw.mit.edu/resources/res-2-002-finite-element-procedures-for-solids-and-structures-spring-2010/>.
- Belton, P. (2021) *Building’s hard problem - making concrete green*, *BBC Technology of Business*. Available at: <https://www.bbc.com/news/business-56716859> (Accessed: 9 August 2021).
- Bertram, N. *et al.* (2019) *Modular construction: From projects to products*, *McKinsey & Company: Capital Projects & Infrastructure*. Available at: <https://www.mckinsey.com/industries/capital-projects-and-infrastructure/our-insights/modular-construction-from-projects-to-products>.
- Borg Costanzi, C. *et al.* (2018) ‘3D Printing Concrete on temporary surfaces: The design and fabrication of a concrete shell structure’, *Automation in Construction*, 94(August 2017), pp. 395–404. doi: 10.1016/j.autcon.2018.06.013.
- Congiu, E., Fenu, L. and Briseghella, B. (2021) ‘Comparison of Form-finding Methods to Shape Concrete Shells for Curved Footbridges’, *Structural Engineering International*. doi: 10.1080/10168664.2021.1878974.
- Correia, R. (2021) *Serviceability assessment of reinforced concrete buildings with non-linear analysis, based on information generated by BIM models*. Universita do Minho.
- Dallinger, S. and Kollegger, J. (2008) ‘Thin post-tensioned concrete shell structures’, in *Proceedings of the International FIB Symposium 2008 - Tailor Made Concrete Structures: New Solutions for our*

Society, p. 158. doi: 10.1201/9781439828410.ch114.

Davis, D. (2013) *Modelled on Software Engineering: Flexible Parametric Models in the Practice of Architecture*. RMIT University.

Eastman, C. (1974) *An outline of the Building Description System, Pennsylvania Institute of Physical Planning*. Pittsburg.

Fernandes, L. P. B. (2015) *An integrated model for simulation of construction phasing of arch concrete dams*. University do Minho.

Goldbach, A. K. *et al.* (2020) ‘CAD-Integrated Parametric Lightweight Design With Isogeometric B-Rep Analysis’, *Frontiers in Built Environment*, 6(April), pp. 1–11. doi: 10.3389/fbuil.2020.00044.

Gomes, C. *et al.* (2018) ‘An integrated framework for multi-criteria optimization of thin concrete shells at early design stages’, *Advanced Engineering Informatics*, 38(June), pp. 330–342. doi: 10.1016/j.aei.2018.08.003.

Gomes, C. (2021) ‘Design Optimisation and Simulation’. Braga: BIM A+ Module 3: Parametric Modelling in BIM Lecture.

Hadilou, A. (2014) ‘Flexible formwork: a methodology for casting funicular structures’, in *Digital Crafting [7th International Conference Proceedings of the Arab Society for Computer Aided Architectural Design (ASCAAD 2014)]*.

Herr, C. M. and Kvan, T. (2007) ‘Adapting cellular automata to support the architectural design process’, *Automation in Construction*, 16(1), pp. 61–69. doi: 10.1016/j.autcon.2005.10.005.

Hughes, T. J. R., Cottrell, J. A. and Bazilevs, Y. (2005) ‘Isogeometric analysis: CAD, finite elements, NURBS, exact geometry and mesh refinement’, *Computer Methods in Applied Mechanics and Engineering*, 194(39–41), pp. 4135–4195. doi: 10.1016/j.cma.2004.10.008.

Iacovidou, E. *et al.* (2021) ‘Digitally enabled modular construction for promoting modular components reuse: A UK view’, *Journal of Building Engineering*, 42(June), p. 9. doi: 10.1016/j.jobe.2021.102820.

Kontovourkis, O., Phocas, M. C. and Katsambas, C. (2019) ‘Digital to physical development of a reconfigurable modular formwork for concrete casting and assembling of a shell structure’, *Automation in Construction*, 106(July), p. 23. doi: 10.1016/j.autcon.2019.102855.

Lock Block (2021) *Lock Block Homepage, Lock Block Ltd*. Available at: <https://www.lockblock.com/> (Accessed: 23 August 2021).

Lomholt, I. (2021) ‘Striatus Masonry Footbridge in Venice: Zaha Hadid Architects’, *e-architect*. Available at: <https://www.e-architect.com/venice/striatus-masonry-footbridge-venice>.

Long, A. *et al.* (2014) ‘FlexiArch: From concept to practical applications’, *Structural Engineer*, 92(7), pp. 10–15.

Lopez, D. and Froese, T. M. (2016) ‘Analysis of Costs and Benefits of Panelized and Modular Prefabricated Homes’, *Procedia Engineering*, 145, pp. 1291–1297. doi: 10.1016/j.proeng.2016.04.166.

Nassar, K. and Aly, E. A. (2012) ‘Automated planning and design of formwork for freeform shell structures’, in *Construction Research Congress 2012: Construction Challenges in a Flat World, Proceedings of the 2012 Construction Research Congress*, pp. 1165–1174. doi: 10.1061/9780784412329.117.

- Pedersen, O. E., Larsen, N. M. and Pigram, D. (2015) 'Post-tensioned Discrete Concrete Elements Developed For Free-form Construction', in Block, P. et al. (eds) *Advances in Architectural Geometry 2014*. London. doi: 10.1007/978-3-319-11418-7.
- Polat, G. (2008) 'Factors Affecting the Use of Precast Concrete Systems in the United States', *Journal of Construction and Engineering Management*, 134(3), pp. 169–178. doi: 10.1061/(asce)1076-0431(2000)6:3(79).
- Popescu, M. et al. (2021) 'Structural design, digital fabrication and construction of the cable-net and knitted formwork of the KnitCandela concrete shell', *Structures*, 31(January 2020), pp. 1287–1299. doi: 10.1016/j.istruc.2020.02.013.
- Ribeirinho, M. J. et al. (2020) *The next normal in construction*, McKinsey & Company.
- Rippmann, M. and Block, P. (2013) 'Funicular shell design exploration', in *ACADIA 2013: Adaptive Architecture - Proceedings of the 33rd Annual Conference of the Association for Computer Aided Design in Architecture*, pp. 337–346.
- Schuster, P. (2017) *FEA 01: What is FEA?* Available at: <https://www.youtube.com/watch?v=sSaUHDQf204> (Accessed: 11 August 2021).
- Schwaber, K. and Sutherland, J. (2015) *The Scrum Guide, Software in 30 Days*. doi: 10.1002/9781119203278.app2.
- Shay Murtagh (2021) *Shay Murtagh Homepage, Shay Murtagh*. Available at: <https://www.shaymurtagh.co.uk/precast-concrete-products/tunnel-segments/> (Accessed: 23 August 2021).
- Stasiuk, D. (2018) 'Design Modeling Terminology', *Proving Ground*, p. 6.
- Stout, J. (2021) 'Shetland fires "should act as warning to modular building industry"', *BBC News*. Available at: <https://www.bbc.com/news/uk-scotland-north-east-orkney-shetland-57942459>.
- Tomás, A. and Martí, P. (2010) 'Shape and size optimisation of concrete shells', *Engineering Structures*, 32(6), pp. 1650–1658. doi: 10.1016/j.engstruct.2010.02.013.
- Turner & Townsend (2018) *International construction market survey 2018, Global rebalancing: a changing landscape*.
- United Nations (2015) *17 Sustainable Development Goals, Department of Economic and Social Affairs*. Available at: <https://sdgs.un.org/goals> (Accessed: 24 August 2021).
- Veenendaal, D. and Block, P. (2012) 'An overview and comparison of structural form finding methods for general networks', *International Journal of Solids and Structures*, 49(26), pp. 3741–3753. doi: 10.1016/j.ijsolstr.2012.08.008.
- Vizotto, I. (2010) 'Computational generation of free-form shells in architectural design and civil engineering', *Automation in Construction*, 19(8), pp. 1087–1105. doi: 10.1016/j.autcon.2010.09.004.
- Webb, S. (2021) *Structural issues: the cost of material and the value of labour, Architectural Review*. Available at: <https://www.architectural-review.com/essays/structural-issues-the-cost-of-material-and-the-value-of-labour> (Accessed: 9 August 2021).
- World Economic Forum (2018) *An Action Plan to Accelerate Building Information Modeling (BIM) Adoption, World Economic Forum*.

Zingoni, A. and Enoma, N. (2020) 'Dual-purpose concrete domes: A strategy for the revival of thin concrete shell roofs', *Structures*, 28(November), pp. 2686–2703. doi: 10.1016/j.istruc.2020.10.067.

LIST OF ACRONYMS AND ABBREVIATIONS

AEC	Architecture Engineering, and Construction
API	Application Programming Interface
BEP	BIM Execution Plan
BIM	Building Information Modelling
CAD	Computer-Aided Design
DIANA FEA	Displacement Analyzer Finite Element Analysis
FEA	Finite Element Analysis
FEM	Finite Element Method
Grasshopper	Grasshopper® 3D
IFC	Industry Foundation Class
IGA	Iso-Geometric Analysis
KE	Kinetic Energy
MEP	Mechanical, Electrical, Plumbing
NURBS	Non-Uniform Rational B-Spline
PT	Post-Tensioning
Revit	Autodesk Revit®
Rhino	Rhinoceros® 3D

This page is intentionally left blank

APPENDICES

APPENDIX 1: PYTHON SCRIPT FOR DIANA AUTOMATIC PROPERTY ASSIGNMENT AND CONSTRUCTION PHASING

```
#####
# Program to automate assignment of properties in DIANA
# Python 3.7.3
# By Lombe Mutale with input from Prof. MA, Prof. BF & CG
#####
setUnit( "LENGTH", "MM" )
setUnit( "FORCE", "N" )

#Create materials
addMaterial( "Concrete", "CONCR", "LEI", [ ] )
setParameter( "MATERIAL", "Concrete", "LINEAR/ELASTI/YOUNG", 30000 )
setParameter( "MATERIAL", "Concrete", "LINEAR/MASS/DENSIT", 2.5e-09 )
setParameter( "MATERIAL", "Concrete", "LINEAR/ELASTI/POISON", 0.2 )

addMaterial( "Steel", "REINFO", "LINEAR", [ "FRLGTH", "NOBOND" ] )
setParameter( "MATERIAL", "Steel", "LINEAR/ELASTI/YOUNG", 200000 )
setParameter( "MATERIAL", "Steel", "FREELE/FRLGTH", 1 )

#add Selfweight
addSet( "GEOMETRYLOADSET", "Dead load" )
createModelLoad( "Global Load 1", "Dead load" )

#add PT loads

addSet( "GEOMETRYLOADSET", "PT load" )
createBodyLoad( "PT load", "PT load" )
setParameter( "GEOMETRYLOAD", "PT load", "LODTYP", "POSTEN" )
setParameter( "GEOMETRYLOAD", "PT load", "POSTEN/TENTYP", "ONEEND" )
setParameter( "GEOMETRYLOAD", "PT load", "POSTEN/ONEEND/FORCE1", 40000 )
setParameter( "GEOMETRYLOAD", "PT load", "POSTEN/SHEAR", 0 )

nB = 140 #ENTER NUMBER OF BLOCKS
nC = nB*4
noOfBlocks = range(1,nB+1)
noOfCables = range(1,nC+1)
#noOfSupports = [1, 2, 3, 5, 9, 10, 19, 20, 21, 22, 35, 36, 37, 38, 55, 56, 57,
58, 79, 80] #ENTER BLOCKS WITH SUPPORTS or add manually in DIANA
listSizeCables = len(noOfCables)
noOfCablesInBlocks = range(1, nC, 4)

rename( "SHAPESET", "Shapes", "Blocks" )

#ASSIGN CABLE PROPERTIES
for Cn in noOfCables:
    setShapeType( "REINFORCEMENTSHAPE", [ "Cable"+str(Cn)] )
    addGeometry( "Cable"+str(Cn), "RELINE", "REBAR", [ ] )
    setParameter( "GEOMET", "Cable"+str(Cn), "REIEMB/CROSSE", 140 )
    setReinforcementType( "REINFORCEMENTSHAPE", [ "Cable"+str(Cn) ], "BAR" )
    assignMaterial( "Steel", "REINFORCEMENTSHAPE", [ "Cable"+str(Cn) ] )
    assignGeometry( "Cable"+str(Cn), "REINFORCEMENTSHAPE", [ "Cable"+str(Cn)] )
```



```

#ASSIGN BLOCK PROPERTIES
for Bn in noOfBlocks:
    setElementClassType( "SHAPE", [ "Block"+str(Bn)], "STRSOL" )
    assignMaterial( "Concrete", "SHAPE", [ "Block"+str(Bn) ] )

    #add Blocks to set
    moveToShapeSet( [ "Block"+str(Bn)], "Blocks" )

    #Relate cables to Blocks
    addSet( "GEOMETRYREINFOSET", "Reinforcements"+str(Bn) )
    rename( "SHAPESET", "Reinforcements"+str(Bn), "Cables Block"+str(Bn) )
ASSIGN REBAR PROPERTIES
for CBn in noOfCablesInBlocks:
    moveToShapeSet( [ "Cable"+str(CBn), "Cable"+str(CBn+1), "Cable"+str(CBn+2),
"Cable"+str(CBn+3)], "Cables Block"+str(int(CBn/4+1)) )

    #add loads - VERTICAL CABLES
    attachTo( "GEOMETRYLOAD", "PT load", "POSTEN/ONEEND/PNTS1", "Cable"+str(CBn),
[[ 4367.39, -1948.74, 11.7079 ]]) #ADD COODINATES OF FIRST END
    attach( "GEOMETRYLOAD", "PT load", [ "Cable"+str(CBn) ] )

    attachTo( "GEOMETRYLOAD", "PT load", "POSTEN/ONEEND/PNTS1",
"Cable"+str(CBn+1), [[ 4683.85, -1974.12, 11.7364 ]]) #ADD COODINATES OF FIRST
END
    attach( "GEOMETRYLOAD", "PT load", [ "Cable"+str(CBn+1) ] )

    #add loads - HORIZONTAL CABLES
    attachTo( "GEOMETRYLOAD", "PT load", "POSTEN/ONEEND/PNTS1",
"Cable"+str(CBn+2), [[ 4074.08, -1703.99, 322.817 ]]) #ADD COODINATES OF FIRST
END
    attach( "GEOMETRYLOAD", "PT load", [ "Cable"+str(CBn+2) ] )

    attachTo( "GEOMETRYLOAD", "PT load", "POSTEN/ONEEND/PNTS1",
"Cable"+str(CBn+3), [[ 4093.40, -1453.85, 654.538 ]]) #ADD COODINATES OF FIRST END
    attach( "GEOMETRYLOAD", "PT load", [ "Cable"+str(CBn+3) ] )

#Add supports
addSet( "GEOMETRYSUPPORTSET", "Geometry support set 1")
createSurfaceSupport( "Support 1", "Geometry support set 1")
setParameter( "GEOMETRYSUPPORT", "Support 1", "AXES", [ 1, 2 ] )
setParameter( "GEOMETRYSUPPORT", "Support 1", "TRANSL", [ 1, 1, 1 ] )
setParameter( "GEOMETRYSUPPORT", "Support 1", "ROTATI", [ 0, 0, 0 ] )

#for nS in noOfSupports:#ADD MANUALLY IF NOT WORKING
    #attach( "GEOMETRYSUPPORT", "Support 1", "Block"+str(nS), [[1000, -
1000, -12.941931]]) )
    #setViewPoint( "ISO1" )

for Bn in noOfBlocks:
#Generate MESH
    setElementSize( [ "Block"+str(Bn)], 100, -1, True )
    setMesherType( [ "Block"+str(Bn)], "HEXQUAD" )
    clearMidSideNodeLocation( [ "Block"+str(Bn) ] )

#RUN ANALYSIS
generateMesh( [] )
#runSolver( [] )
#showView( "RESULT" )

```

```

#set up non-staged analysis (full structure)
addAnalysis( "Analysis1" )
addAnalysisCommand( "Analysis1", "LINSTA", "Structural linear static" )
setAnalysisCommandDetail( "Analysis1", "Structural linear static",
"OUTPUT(1)/SELTYP", "USER" )
addAnalysisCommandDetail( "Analysis1", "Structural linear static", "OUTPUT(1)/USER"
)
addAnalysisCommandDetail( "Analysis1", "Structural linear static",
"OUTPUT(1)/USER/STRESS(1)/TOTAL/CAUCHY/PRINCI" )
addAnalysisCommandDetail( "Analysis1", "Structural linear static",
"OUTPUT(1)/USER/DISPLA(1)/TOTAL/TRANSL/GLOBAL" )
addAnalysisCommandDetail( "Analysis1", "Structural linear static",
"OUTPUT(1)/USER/STRESS(2)/TOTAL/CAUCHY/GLOBAL" )
addAnalysisCommandDetail( "Analysis1", "Structural linear static",
"OUTPUT(1)/USER/STRAIN(1)/TOTAL/GREEN/GLOBAL" )

#set up staged analysis
addAnalysis( "Analysis2" )
renameAnalysis( "Analysis2", "Analysis2" )
renameAnalysis( "Analysis2", "Simulation Analysis" )
addAnalysisCommand( "Simulation Analysis", "STAGCO", "Geomechanical staged
construction" )
renameAnalysisCommand( "Simulation Analysis", "Geomechanical staged construction",
"Staged construction" )

#ADD A STAGE - FIRST STAGE
addAnalysisCommandDetail( "Simulation Analysis", "Staged construction", "STAGE" )
renameAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"STAGE(1)", "Stage1" )

setAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"STAGE(1)/PHREAT/LVLTYP", "NONE" )
setAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"STAGE(1)/INISTR", False )

#Add loads to stage
setActivePhase( "Simulation Analysis", "Stage1" )
addAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"STAGE(1)/LODLEV/LOAD" )
addAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"STAGE(1)/LODLEV/LOAD(1)/LOADNR" )
setAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"STAGE(1)/LODLEV/LOAD(1)/LOADNR", 2 )

#Disable all
setActiveInPhase( "Simulation Analysis", "SHAPESET", [ "Blocks" ], [ "Stage1" ],
False )

for Bn in noOfBlocks:
    setActiveInPhase( "Simulation Analysis", "GEOMETRYREINFOSET", [ "Cables
Block"+str(Bn) ], [ "Stage1" ], False )

#Enable some
setActiveInPhase( "Simulation Analysis", "SHAPE", [ "Block1" ], [ "Stage1" ], True
)
setActiveInPhase( "Simulation Analysis", "GEOMETRYREINFOSET", [ "Cables Block1"], [
"Stage1" ], True )

```

```

#Enable some

setActiveInPhase( "Simulation Analysis", "SHAPE", [ "Block1" ], [ "Stage1" ], True
)
setActiveInPhase( "Simulation Analysis", "GEOMETRYREINFOSET", [ "Cables Block1"], [
"Stage1" ], True )

noOfStages = range(2, len(noOfBlocks)+1)


for Stn in noOfStages:
    copyAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"STAGE("+str(Stn-1)+")", "" )
    renameAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"STAGE("+str(Stn)+")", "Stage"+str(Stn) )
    setActiveInPhase( "Simulation Analysis", "GEOMETRYREINFOSET", [ "Cables
Block"+str(Stn) ], [ "Stage"+str(Stn) ], True )
    setActiveInPhase( "Simulation Analysis", "SHAPE", [ "Block"+str(Stn) ], [
"Stage"+str(Stn) ], True )

setAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"OUTPUT(1)/SELTYP", "USER" )
addAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"OUTPUT(1)/USER" )
addAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"OUTPUT(1)/USER/STRESS(1)/TOTAL/CAUCHY/PRINCI" )
addAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"OUTPUT(1)/USER/DISPLA(1)/TOTAL/TRANSL/GLOBAL" )
addAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"OUTPUT(1)/USER/STRESS(2)/TOTAL/CAUCHY/GLOBAL" )
addAnalysisCommandDetail( "Simulation Analysis", "Staged construction",
"OUTPUT(1)/USER/STRAIN(1)/TOTAL/GREEN/GLOBAL" )


```


APPENDIX 2: DIANA MODELLING AND ANALYSIS PROCEDURE

1. Setting up the project







2. Creating the geometry






3. Adding a material and assigning material characteristics







4. Assigning shapes to geometry. Shapes can be either geometry or reinforcement





5. Assigning material to the shapes and Element class to the geometry







6. Adding loads to the shapes






7. Adding supports







8. Adding analysis






9. Assigning mesh properties





The PT load, assigned to the post tensioning cables, is to be added to each analysis stage after generating the mesh.



APPENDIX 3: PART GRASSHOPPER CODE FOR FORM-FINDING AND SHAPE GENERATION

Cable lines generation procedure

